

Submitted to:  
US EPA Region 8  
Denver, CO

Submitted by:  
Atlantic Richfield Company  
La Palma, CA  
October 2013

# Adit and Portal Investigation Report 2013 Update

## Rico-Argentine Mine Site – Rico Tunnels Operable Unit OU1 Rico, Colorado

October 2013




# Adit and Portal Investigation Report 2013 Update

## Rico-Argentine Mine Site – Rico Tunnels Operable Unit OU1 Rico, Colorado



---

Prepared By Douglas M. Yadon, PE  
Certifying Engineer



---

Reviewed By Elliott D. Drumright, PE  
Senior Geotechnical Engineer



---

Released By Thomas M. Kreutz, PE  
Project Manager



# Atlantic Richfield Company

Atlantic Richfield Company

4 Centerpointe Drive, 4-435  
La Palma, CA 90623  
Direct: (714) 228-6770  
Fax: (714) 228-6749  
E-mail: Anthony.Brown@bp.com

October 30, 2013

## **VIA EMAIL AND HAND DELIVERY**

Mr. Steven Way  
On-Scene Coordinator  
Emergency Response Program (8EPR-SA)  
US EPA Region 8  
1595 Wynkoop Street  
Denver, CO 80202-1129

**Subject: Adit and Portal Investigation Report – 2013 Update  
Rico Argentine Mine Site – Rico Tunnels Operable Unit OU01 Rico, Colorado**

Dear Mr. Way,

A digital file in PDF format of the Adit and Portal Investigation Report – 2013 Update, Rico Argentine Mine Site – Rico Tunnels Operable Unit OU01 Rico, Colorado, dated October 30, 2013, is being submitted to you today via email. Three (3) hard copies of the report will also be hand-delivered to your office no later than close of business November 1.

Atlantic Richfield Company (AR) is submitting this report responsive to requirements in Task D of the Removal Action Work Plan accompanying the Unilateral Administrative Order for Removal Action, Rico-Argentine Site, Dolores County, Colorado, U.S. EPA Region 8, Docket No. CERCLA-08-2011-0005.

Please note that this report presents all relevant investigation results from studies prior to 2013, and those preliminary results from ongoing field investigations that were available as of the date of this submittal. AR proposes to complete the field investigations and laboratory testing this fall, and to compile, interpret and document the 2013 results in a final version of this report to be submitted not later than January 30, 2014.

If you have any questions, please feel free to contact me at (951) 265-4277.

Sincerely,



Anthony R. Brown  
Project Manager  
Atlantic Richfield Company



cc: Ronald Halsey, Atlantic Richfield Company (via e-mail)  
Terry Moore, Atlantic Richfield Company (via e-mail)  
Sheila D'Cruz, Atlantic Richfield Company (via e-mail)  
Reginald Ilao, Atlantic Richfield Company (via e-mail and hardcopy)  
Jan Christner, Weston Solutions, Inc. (via e-mail)  
William Duffy, Esq., Davis, Graham & Stubbs, LLP (via e-mail)  
Adam Cohen, Esq., Davis Graham & Stubbs, LLP (via e-mail)  
Sandy Riese, EnSci, Inc. (via e-mail)  
Tom Kreutz, AECOM Technical Services, Inc. (via e-mail)  
Doug Yadon, AECOM Technical Services, Inc. (via e-mail)  
Chris Sanchez, Anderson Engineering Company, Inc. (via e-mail)  
Kristine Burgess, AEEC, LLC (via e-mail)  
Marc Lombardi, AMEC Environment & Infrastructure, Inc. (via e-mail)  
Spencer Archer, AMEC Environment & Infrastructure, Inc. (via e-mail)



A BP affiliated company



# Contents

<b>1.0 Introduction .....</b>	<b>1</b>
1.1 Purpose and scope.....	1
1.2 Organization.....	1
<b>2.0 Site Reconnaissance and Ground Surveys .....</b>	<b>2</b>
<b>3.0 Field Exploration.....</b>	<b>3</b>
3.1 Engineering geologic mapping.....	3
3.2 Test pitting.....	3
3.3 Drilling .....	3
3.3.1 Drilling equipment and methods.....	3
3.3.2 2011 drilling results.....	4
3.3.3 2012 drilling results.....	5
3.3.4 2013 drilling results.....	6
3.4 Downhole geophysical logging.....	7
3.5 Surface geophysical profiling .....	7
3.5.1 Refraction microtremor .....	7
3.5.2 Electrical resistivity.....	8
3.6 Groundwater level monitoring .....	8
<b>4.0 Geotechnical Laboratory Testing .....</b>	<b>9</b>
4.1 Test methods and results - 2011.....	9
4.2 Test methods and results – 2012.....	9
<b>5.0 Site Characterization .....</b>	<b>10</b>
5.1 St. Louis tunnel .....	10
5.2 Site geology .....	11
5.3 Geologic units .....	11
5.3.1 Colluvium .....	11
5.3.2 Bedrock.....	11
<b>6.0 References.....</b>	<b>12</b>



## List of Appendices

Appendix A      Field Investigations

Appendix B      Geotechnical Testing

## List of Tables

Table 3.1          Groundwater Elevations

Table 4.1          Geotechnical Laboratory Testing Results

## List of Figures

Figure 1.1          Site Location Map

Figure 2.1          2011 Ground Survey

Figure 2.2          2013 Ground Survey

Figure 3.1          Field Investigation Plan

Figure 5.1          Geologic Map

Figure 5.2          Geologic Profile



## List of Acronyms

AECI	Anderson Engineering Company, Inc.
AIP	Adit Investigation Plan
EPA	Environmental Protection Agency
ER	electrical resistivity
FSP	Field Sampling Plan
HAS	hollow stem auger
PVC	polyvinyl chloride
ReMi	Refraction Microtremor
RQD	Rock quality designation
SLT	St. Louis Tunnel
SPT	Standard Penetration Test
ST	Shelby Tube



# 1.0 Introduction

## 1.1 Purpose and scope

This document updates the initial Adit and Portal Investigation Report submitted as Part D of the 2011 Investigations, Analyses and Evaluations report (Atlantic Richfield Company, 2011a) required under Subtask D1 of the Remedial Action Work Plan (RAWP) for the Rico-Argentine Mine Site (EPA, 2011). This updated report documents the work accomplished to date pursuant to the program of site investigations and laboratory testing in the approved original Investigation Plan for Collapsed Adit Area at St. Louis Tunnel (referred to as the Adit Investigation Plan or AIP) (Atlantic Richfield Company, 2011b), the Supplement to the Investigation Plan for Collapsed Adit Area at St. Louis Tunnel (Atlantic Richfield Company, 2012; referred to as the Supplement to the AIP), and the 2013 Supplement to the Investigation Plan for Collapsed Adit Area at St. Louis Tunnel (AECOM, 2013a; referred to as the 2013 Supplement to the AIP). The location of the adit collapse area relative to the St. Louis Ponds site is shown on Figure 1.1.

The primary objectives of the investigations as described in the AIPs were to:

- Investigate the condition of the collapsed portion of the adit and how it interfaces with competent rock at the brow of CHC Hill;
- Assess the possible accumulation of settled solids and water build-up behind the existing blockage in the collapsed area; and
- Provide information to support design of a hydraulic control system for discharges from the St. Louis Tunnel (referred to herein as the SLT).

Investigations to support achieving these objectives are focused on collecting, controlling, and conveying the adit flow from its current point of discharge to the water treatment facility ultimately selected as part of the overall remedy at the Rico Tunnels Operable Unit OU01. It is currently assumed that the discharges will be conveyed to the upgradient end of the demonstration wetlands currently being constructed in the former Pond 19 area (immediately north of Pond 18).

The investigations completed during 2011 and 2012, and results to date from the 2013 investigation program provide the key information necessary to identify appropriate alternatives to advance to 30 percent design, and then support final design of the selected alternative as described in the Preliminary Design Report, St. Louis Tunnel Hydraulic Control Measures (Atlantic Richfield Company, 2013b).

## 1.2 Organization

Section 1.0 of this report describes the purpose and scope of the investigations performed to meet the objectives of the RAWP and the associated investigation plans. Site reconnaissance and ground surveys are documented in Section 2.0. The locations, methodologies and results of the various field investigation techniques implemented at the site are described in Section 3.0. Section 4.0 presents the results of geotechnical testing performed to date. An interpretation of geologic and geotechnical conditions in the adit collapse area is presented in Section 5.0. References are provided in Section 6.0.

Note that results of geochemical analyses of mine waters encountered during the original field exploration program in 2011 and periodic sampling of borings AT-02 and BAH-01 are included in data previously transmitted to EPA and posted on the project SharePoint site.



## 2.0 Site Reconnaissance and Ground Surveys

Detailed site reconnaissance of the portion of the St. Louis Tunnel exposed in the U-shaped excavation behind the existing structure at the historic portal location (i.e., the adit collapse area, also referred to as the open, collapsed tunnel reach) was conducted in 2011 and again in 2013. Plans for detailed surveying of key visible features were developed based on the reconnaissance efforts and review of all available, relevant historic information. Targets selected for survey included the tops of timber posts and beams that were key elements of the tunnel support in this reach and that appeared to still be in approximately their original position, and still visible remnants of the original concrete portal structure and railroad bridge abutments immediately behind the portal entrance. Surveys of specific features were conducted utilizing conventional total station equipment and techniques in 2011. In 2013 ground-based LIDAR was utilized to develop 1-foot contours in the study area, as well as to identify the locations and elevations of key features as noted above. Appropriate safety precautions were implemented to protect the survey crews when working near the collapsed tunnel.

The main objective of ground surveys at the adit collapse area was to determine to the extent feasible the dimensions, alignment (i.e., bearing or azimuth) and grade of the visible portion of the tunnel. It was reasoned that this information would provide a check on the tunnel bearing and grade interpreted from published information in McKnight (1974) and unpublished mapping of tunnel geology (Anonymous; date unknown but believed to be circa mid-1950s). The historic and new survey data provided the basis on which a best fit interpretation of portal location, bearing (azimuth) and grade of the St. Louis Tunnel was developed. This interpretation was used to target the initial inclined borings drilled in 2011 and additional inclined borings attempted in 2012 and planned to be drilled in 2013 as discussed in Section 4.0.

Figure 2.1 shows the key data acquired from the 2011 ground survey and an interpreted “best fit” bearing (or azimuth) of the tunnel based on that data. The nominal grade calculated by averaging the top elevations of selected apparently in-place timber posts was 0.9 percent. This is very close to the typical grade constructed in mines of this type and era of about one (1) percent. However, the reliability of this estimate of tunnel grade was judged potentially suspect due to the inherent variability of the ground at the tunnel support post locations (and thus likely variable length of the posts) and the potential that the posts had settled differentially over time under the prior load of colluvium over the tunnel roof. In spite of these uncertainties, drilling of borings AT-02 and BAH-01 in 2011 successfully intercepted the tunnel.

Additional ground survey was performed in 2013, concentrating on spot surveys at the location of the original portal structure (located at and now a portion of the subsequently constructed lime addition structure that is present today). In addition, updated topographic mapping at one-foot contour interval was developed from the ground LIDAR survey. Figure 2.2 provides the updated topographic base mapping developed in 2013. The location and bearing of the tunnel were refined based on the data from the new surveys and the locations at which the tunnel was intercepted by drilling AT-02 and BAH-01 in 2011. The floor grade from the historic tunnel geologic map (found after the drilling in 2011) of approximately 0.3 percent was adopted as the best available information on grade. Note that the approximate locations on the tunnel periphery that were intercepted by AT-2 and BAH-01 were inferred from the drilling data, but are not known with certainty. As a result, the drilling data was not sufficient to check the 0.3 percent grade assumption.



## 3.0 Field Exploration

### 3.1 Engineering geologic mapping

A site reconnaissance was performed to identify and map surficial materials (such as fill, alluvium, colluvium, and landslide deposits), and major bedrock units that occur in the vicinity of the overall Rico project site. Prior to the field work, available published geologic mapping and reports were reviewed. The site geologic reconnaissance was performed by traversing the site on foot and mapping key geologic features, exposures and unit contacts on available topographic maps of the site and vicinity. The results of the geologic mapping are discussed in Section 5.0 and shown on Figure 5.1.

### 3.2 Test pitting

A total of five (5) test pits (TP2011-AT1, -AT-2, -AT-3, -AT-5 and -AT-6) were hand dug in 2011 at the locations shown on Figure 3.1 to acquire representative bulk samples of the colluvium supporting the existing steep and metastable slopes of the excavation in the collapsed adit area. TP2011-AT4 was not dug due to safety issues at its planned location. In addition to acquiring samples for laboratory testing as described in Section 4.1, the in situ density and moisture content of the colluvium was measured utilizing a nuclear density gage at four (4) of the test pit locations (TP2011-AT1, -AT2, -AT5 and -AT6). The results of the field density testing are included in Table 4.1. Note that logs were not developed for these very shallow hand-dug excavations.

Three (3) test pits (TP2013-6, -7 and -8) were excavated with a tracked excavator to depths ranging from 7.0 to 18.5 feet at the locations shown on Figure 3.1 (at the entrance to the terrain trap, adjacent to the open, collapsed reach of the SLT, and in the colluvium in the adjacent slope to the south). The primary objective of these test pits was to provide bulk samples of the colluvium for additional geotechnical testing as described in Section 4.1. Logs and photographs of the test pits are provided in Appendix A and the results of geotechnical testing are included in Table 4.1.

### 3.3 Drilling

Boreholes were drilled to investigate subsurface stratigraphy, geotechnical properties, and groundwater conditions, and to collect samples for geotechnical laboratory testing, at targeted locations within and adjacent to the open, collapsed reach of the SLT and terrain trap. The boreholes were drilled to the target depths (or refusal if shallower) specified in the original AIP, Supplement to AIP, or 2013 Supplement to the AIP and logged by a professional geotechnical engineer or geologist in general accordance with the guidelines in the Engineering Geology Field Manual (US Bureau of Reclamation, 2001). The logs include information on the following:

- Drilling equipment used
- Difficult or problematic conditions
- Depth of changes in horizons or materials encountered, including color, gradation, soil classification, plasticity, density and moisture
- Other features such as roots, debris, fissures, voids, staining, etc.
- If encountered, the depth to perched or water table groundwater

#### 3.3.1 Drilling equipment and methods

A variety of drilling equipment and methods have been utilized at the site over the past three field seasons in an effort to accommodate the challenging drilling conditions inherent to the colluvial and



alluvial deposits present. The equipment and methods used each season are briefly described as follows.

#### **2011:**

- Boart-Longyear C-100 - "Minis Sonic" tracked sonic drill rig used for vertical sonic drilling in restricted access locations
- Boart-Longyear 600 C – Standard-size tracked sonic drill rig used for vertical sonic drilling in typical access locations and Standard Penetration Test (SPT) and Shelby Tube sampling
- Longyear 45: Skid-mounted core drilling rig used for angled borings advanced using direct mud rotary drilling and casing advance

#### **2012:**

- AMS Compact Roto-Sonic 10-C - Light-duty small-tracked sonic rig with 2-inch barrel used for angled sonic and mud rotary drilling, and SPT and Shelby Tube sampling (if applicable) in typical surficial deposits on site; used in restricted access locations as needed
- Ditch Witch JT860 and Symmetrix System - Small, track-mounted rotary drill rig used for angled air rotary drilling, advancing casing with the Symmetrix casing-advance system
- Central Mining Equipment 85 - Large truck-mounted, rotary drill rig used for hollow stem auger (HSA) drilling through typical colluvium and alluvium and mud-rotary drilling (if needed) through cobbles and boulders, with SPT testing and sampling

### **3.3.2 2011 drilling results**

Two drill holes (AT-2 and BAH-01) were completed in 2011 as part of the initial investigations at the adit collapse area. Copies of the boring logs for AT-2 and BAH-01 are included in Appendix A. Detailed narratives of the methods used and conditions encountered in drilling AT-2 and BAH-01 are included in Atlantic Richfield Company (2011a, Part A), and summarized as follows.

**AT-2.** Drill hole AT-2 was originally planned to be drilled using an air-track rig and the designation of "AT" was retained when the decision was made to drill with a direct mud rotary coring rig instead. The final location selected for this drill hole was in the vicinity of the originally planned AT-2; there was not a drill hole attempted at the AT-1 or other locations envisioned in Atlantic Richfield Company (2011b) due to safety concerns working in the terrain trap. A drilling platform approximately 20 feet by 40 feet was constructed and concrete blocks were stacked on the up-slope side of the platform to prevent rocks rolling down the terrain trap slopes from impacting the drilling platform. A skid-mounted Longyear 45 core drilling rig was positioned on the drilling platform and the drill stem oriented to intersect the St. Louis Tunnel based on the best location information available at that time. Drill hole AT-2 was drilled between October 18 and 21, 2011.

The hole was advanced through colluvium and into the tunnel by mud rotary drilling and advancing HWT casing. At the angle penetrated, the tunnel void was approximately 8.5 feet long. An attempt was made to core into the ground beyond the tunnel with HQ wireline tooling. Steel and wood were encountered that were interpreted as a tie and rail. Once cleared, a further attempt was made to core past the tunnel. It is believed that the hole terminated approximately 7 feet into colluvium beyond the tunnel. The hole was completed with nominal 4-inch diameter HWT casing penetrating into the tunnel. Water level in the tunnel was measured and samples of tunnel water and accumulated settled sludge ("red dog") were sampled through the casing.

**BAH-01.** Boring BAH-01 was drilled to investigate the thickness of the colluvial material and location of the buried bedrock surface in the vicinity of the St. Louis Tunnel alignment. The boring was oriented to attempt to intercept the St. Louis Tunnel. The location of BAH-01 and orientation of the borehole in



relation to the St. Louis Tunnel alignment are illustrated on Figure 3.1. Drilling was accomplished using the same skid mounted Longyear 44 diamond core rig as for AT-2. The hole was advanced through the colluvium using rotary wash methods. Drilling commenced on October 26 and was completed on November 9, 2011.

Drilling conditions in the colluvium from ground surface to 210 feet (inclined boring length) were very difficult. The difficulties can be attributed to the fact that the colluvium encountered in the borehole was unstable in that portions of uncased hole would typically cave if the drill stem would have to be pulled back from the bottom of the hole for any reason. Another challenge for completion of the borehole was the fact that the colluvium contained blocks of hard bedrock that were very difficult to penetrate to set casing to stabilize the hole. The colluvium was also relatively loose such that larger blocks of bedrock encountered in the colluvium tended to move during drilling and sometimes bind the drill stem. The thickness of the colluvium was unknown prior to drilling. For this reason, careful sampling of the larger bedrock blocks using diamond coring was necessary to determine if the borehole was penetrating intact bedrock or larger blocks of detached bedrock within the colluvium. In addition, installation of casing using a casing shoe (that was required from 147 to 210 feet) could not be accomplished through harder bedrock blocks unless these blocks were predrilled using a diamond core bit and core barrel. The borehole was completed by installing steel casing through the colluvium and into the surface of the bedrock. The casing includes: 1) a larger casing (HWT casing) that extends from the surface to 186 feet; and 2) a smaller casing (HQ rods) that extends from the surface to 210 feet. Both sets of casing were left in the completed boring so that the hole would remain open and accessible for future surveys and sampling as necessary.

Bedrock was encountered between 210 and 240 feet in the boring. The bedrock was sampled by continuous coring. A void zone was encountered between 240 and 252 feet where the boring was terminated. The void was identified by the fact that the drill stem could be advanced by pushing the rods without rotation. When the void was encountered it was suspected to be the St. Louis Tunnel and the rods were pushed for 12 feet in an attempt to determine if drilling could be resumed on the far side of the tunnel. However, bedrock was not encountered within the 12 foot zone suggesting that the drill stem was following the wall of the tunnel rather than penetrating rock on the back (north) side of the tunnel.

After the void was encountered the drill stem was extended approximately five (5) feet into the void and drill fluid was pumped down the drill stem for several minutes in an effort to agitate sediment or precipitate that was thought may be present in the tunnel so that a color change could possibly be detected where the flow from the St. Louis Tunnel daylight in the tunnel collapse reach shown on Figures 5.1 and 5.2. Thirty three minutes after drilling fluids were initially pumped into the tunnel a distinct red color change was noted in the St. Louis Tunnel discharge.

### 3.3.3 2012 drilling results

A total of five (5) borings were drilled at the locations shown on Figure 3.1 during the 2012 field season. The drilling method used and results obtained for each of these borings are described below. Standard 2-inch nominal Schedule 40 PVC open tube wells were installed in selected borings as noted below, utilizing 0.010-inch machine-slotted screen with silica sand pack or pre-pack screens (as noted on the logs). Boreholes not completed as monitoring wells were backfilled using a fluid cement/bentonite grout unless otherwise noted on the logs. Logs for these borings are provided in Appendix A.

**MW-202.** Boring MW-202 was completed within the terrain trap near boring AT-2. This boring was advanced using the sonic drilling method. MW-202 encountered 2 feet of sandy and silty gravel fill at the surface, followed by layered sandy gravel colluvium with variable silt and clay content to the maximum depth of exploration (38.8 feet). Selected intervals of the sonic core recovered were saved as bulk samples for laboratory testing as described in Section 4.0. A 10-foot-long well screen with sand



pack was placed at the bottom of the hole, and then the remainder of the hole was backfilled with a grout seal.

**MW-204.** Boring MW-204 was drilled at the west end of the open, collapsed portion of the SLT utilizing the sonic drilling equipment. MW-204 encountered mostly sandy gravel colluvium with variable silt and clay content from the surface to the maximum depth of exploration (31.5 feet). A 15-foot long well screen and sand pack were set at the bottom of the hole, followed by a grout seal to the ground surface. Selected intervals of the sonic core recovered were saved as bulk samples for laboratory testing as described in Section 4.2.

**CHV-101S.** Boring CHV-101S was drilled on the north side of the open, collapsed portion of the SLT, between MW-202 and MW-204. This boring was advanced using the HSA drilling technique with SPTs performed in situ on approximately 2.5-foot intervals to 30 feet, with a final SPT taken at 45 feet. SPT samples were recovered for laboratory testing as discussed in Section 4.2. Loose, clayey sand fill was encountered from grade to 7.5 feet, followed by mostly silty and clayey sand and gravel colluvium (medium-dense increasing to extremely dense) to refusal on boulders at 29.0 feet. The boring was then offset 6 feet east, blank drilled to 30 feet, then advanced through layered gravel, cobbles, and boulders, again to refusal at 48 feet. It was then decided to terminate the boring, and complete it as an open tube monitoring well with a 10-foot-long well screen and sand pack at the bottom, with a grout seal to the ground surface.

**CHI-102 and -102B.** Boring CHI-102 was intended to be completed as an angle boring through the colluvium to intercept intact bedrock in the SLT east of the colluvial reach of the tunnel. The boring was drilled from a prepared drilling pad approximately 175 feet north of the tunnel. The boring was completed with compressed air as the drilling fluid, using a down-hole hammer/casing assembly. From the surface, and on an initial 22.2 degree down-angle, silty gravel and sand was observed in the cuttings to 5 feet, followed by silty sand with sandstone and shale fragments to 23 feet. From 23 to 38 feet, silt with fragments of altered sandstone was observed. At 38 feet, the welded casing shoe broke off of the casing and the hole was terminated. The casing was left in place.

Boring CHI-102B was a second attempt at the same target as for CHI-102, and was offset 2 feet to the east. The boring extended to 65 feet (at a similar down angle of 21.4 degrees). In a matrix of sandy silt colluvium, fine-grained sandstone chips were observed to 47.5 feet, followed by a boulder from 47.5 to 51.5 feet. From 51.5 to 65 feet, sandstone, quartz, and pyrite fragments were observed in a matrix of sandy silt colluvium. A similar casing/casing shoe problem occurred and the boring was terminated at 65 feet. The casing was left in place.

### 3.3.4 2013 drilling results

A total of five (5) primary vertical borings were completed during the 2013 field season (MW-201, -203, -205, -207 and CHV-101D). Two (2) additional borings (CHV-101M and -101U) were drilled immediately adjacent to CHV-101D to install monitoring wells with screens in perched aquifers encountered during the drilling of CHV-101D. The locations of these borings are shown on Figure 3.1 and logs are included in Appendix A.

**MW-206.** One additional vertical boring (MW-206) was originally planned as noted in the 2013 Supplement to the AIP. A decision was made to delete MW-206 from the 2013 field investigation program given the successful results from the other 2013 borings completed, the results of the nearby 2013 surface geophysical profiling (see Section 3.5), and information acquired from other drilling in the vicinity during prior field investigations.

**CHI-101 and -102C.** Two (2) inclined borings (CHI-101 and -102C), and possibly a third inclined boring (CHI-103) pending results of the first two borings, were originally planned as described in the 2013 Supplement to the AIP. These borings were primarily intended to supplement information within the



rock portion of the existing SLT acquired from boring BAH-01 in 2011 to support a hydraulic control measures alternative involving tunneling or large-diameter horizontal drilling to rock. Boring CHI-101 was drilled to 113 feet, encountering the same extremely challenging drilling conditions in the colluvium as found in BAH-01, CHI-102 and CHI-102B. The planned start of drilling of boring CHI-102C was delayed due to weather-induced instability found in the access road and drill pad on the north side of the terrain trap prior to mobilizing the drill rig to that location. Given the recommendation in the Preliminary Design Report, St. Louis Tunnel Hydraulic Control Measures (subsequent to submittal of the 2013 Supplement to the AIP) to proceed with an alternative for hydraulic control measures that does not involve tunneling or horizontal boring, and with weather conditions deteriorating and safety concerns rising, a decision was made to terminate boring CHI-101 at 113 feet, and not to drill boring CHI-102C (or CHI-103) during the 2013 field season.

### **3.4 Downhole geophysical logging**

All five (5) of the borings completed during the 2013 field investigation and two borings completed in 2012 (MW-202 and -204) were logged with a suite of downhole geophysical tools after the drilling and well installation were completed. The tools utilized included borehole video (for casing assessment), and natural gamma, conductivity, and thermal neutron (for stratigraphy, lithology and saturation).

The downhole geophysical logging was performed by the COLOG Division of Layne Christensen between October 22 and 24, 2013. The downhole logging was performed by lowering the selected tool down the PVC casing within the borehole by a multi-conductor cable connected to a motorized winch. The data collected during the survey was transmitted to a computer and graphical display and reviewed by the geophysical-logging specialist in real time. This allowed for the geophysical-logging specialist to verify that the tools were operating as expected and make appropriate adjustments to the surveys as necessary to meet the data collection objectives.

### **3.5 Surface geophysical profiling**

Surface geophysical profiling was performed by GEI Consultants, Inc. as part of the 2013 field investigation program utilizing two complementary techniques to supplement the results of borings and test pits. The techniques employed were refraction microtremor (ReMi) and electrical resistivity (ER). Each of these techniques is discussed in the following subsections.

#### **3.5.1 Refraction microtremor**

ReMi profiles record ambient vibrations from nearby sources such as moving vehicles and equipment that result in shear and compression wave returns from subsurface materials to a linear array of geophones placed on the ground surface along the profile to be explored. These returns are assembled into a response spectrum that is analyzed by computer to evaluate shear and compression wave velocities (and thereby an index of density) of overburden materials and the approximate depth to interfaces of materials of varying density (e.g., competent strata such as intact bedrock).

A series of geophones were placed on the ground in arrays at a spacing appropriate to the depth of exploration desired. Where multiple spreads were performed to create a long line, the last several geophones were left in place and utilized to create overlap between adjacent spreads. This overlap is necessary to fill in data gaps near profile edges when creating continuous two-dimensional sections on longer lines. Once collected, the data were checked for their fidelity. To assure that a robust profile was being made, both individual recordings and multiple summed (stacked) recordings were evaluated.

A wave field transformation data processing technique and an interactive Rayleigh-wave dispersion modeling tool were employed for the spectral analysis of surface waves. By analyzing segments of the geophysical line and integrating the results, two-dimensional profiles were developed along the seismic



line arrays. The purpose of the two-dimensional profiles was to provide details of the shear wave velocities along the array length to the greatest depths possible.

A total of seven lines of seismic data were collected for ReMi processing from September 25 through October 1, 2013. The locations of these lines as surveyed by Anderson Engineering Company, Inc (AECI) are shown on Figure 3.1. RM-201 through RM-204 were aligned to provide overall areal coverage of the colluvium and alluvium overlying bedrock at some depth at and in the vicinity of the collapsed adit and terrain trap. These alignments were constrained to avoid excessively steep slopes that complicate the interpretation of the field data. The three shorter ReMi lines (RM-205A, -205B, and -205C) located within the terrain trap were aligned to attempt to locate the St. Louis Tunnel and supplement the locations confirmed to date at AT-2 and BAH-01. The results of the ReMi profiling are presented in Appendix A.

### **3.5.2 Electrical resistivity**

Where conditions are susceptible, ER profiling can be used to image unconsolidated sediments/layering, groundwater interfaces of sufficiently contrasting electrical conductivity (due to dissolved mineral chemistry), near-surface geologic stratigraphy, and air/water-filled and clay-filled voids. These features represent zones of variable electrical conductivity, and by mapping the flow of electrical current throughout the subsurface, it is possible to image the lateral and vertical distribution of these features. The objectives of the ER profiling at the open, collapsed reach of the SLT and adjacent ground were to: 1) further characterize the nature and stratigraphy of the colluvium and alluvium underlying the area; 2) identify the approximate depth to saturation within the colluvium (whether due to perched or water table conditions); and 3) to the extent feasible, assess the presence of partial saturation that might indicate water exiting the SLT and seeping into the colluvium.

ER profiling was performed by transmitting a very low amperage direct current (DC) electrical current into the subsurface between stainless steel electrodes spaced equally along a profile. The subsurface current flow was mapped by measuring the electrical potential at the ground surface using a high-sensitivity resistivity meter. Resistivity profiles were positioned for the greatest allowable profile length to facilitate depth of investigation and desired resolution. The longest single profile utilized a 10-foot electrode spacing; a 5-foot electrode spacing was used on the shorter lines. A maximum exploration depth of approximately 45 to 100 feet was targeted using these electrode array lengths. Elevation changes over the length of the deployed resistivity array were picked from the location surveys and existing 1-foot contour topographic mapping and used in the data reduction process.

Four lines of ER profiling (RS-201, RS-202, RS-203, and RS-204) were performed in and adjacent to the open, collapsed reach of the SLT from September 25 through October 1, 2013. As shown on Figure 3.1, these lines were located adjacent to the ReMi lines. The results of the ER profiling are presented in Appendix A.

### **3.6 Groundwater level monitoring**

All of the borings completed as monitoring wells were developed by bailing or surging to clear the well casing and screen of drilling fluid and settled cuttings. Water levels are periodically monitored in accordance with the requirements in the Sampling and Analysis Plan for Surface Water and Groundwater (Atlantic Richfield Company, 2013c). Groundwater level readings to date are presented in Table 3.1.



## 4.0 Geotechnical Laboratory Testing

### 4.1 Test methods and results - 2011

Bulk samples acquired from the hand dug test pits described in Section 3.2 were tested for gradation, plasticity (Atterberg limits) and laboratory moisture/density relationship (i.e., Proctor density). The results of the laboratory testing are included in Table 4.1; laboratory data sheets for this testing are provided in Appendix B. The results of the field density/moisture content testing are included with the laboratory testing results in Table 4.1 and in Appendix A.

Three (3) of the samples tested classify as non-plastic to very low plasticity silty gravel with sand; one sample tested as low plasticity clayey gravel with sand; and the other sample was slightly plastic silty, clayey sand with gravel. The percent fines of the minus 3 to 4 inch fraction of these samples ranged from 13 to 23 percent, averaging 19 percent. Corrected maximum dry density of these samples ranged from 127.2 to 138.0 pcf with optimum moisture contents ranging from 7.6 to 9.3 percent. The in situ density and moisture content from nuclear gage testing ranged from 97.5 to 118.0 pcf and 11.7 to 15.8 percent, respectively. Based on these laboratory moisture-density (i.e., Proctor) test and nuclear gage in situ density results, the near surface colluvium forming the steep excavation slopes in the terrain trap is loose to very loose (relative compaction in the range of only 73-88 percent).

One additional sample from the terrain trap slopes (identified as "St. Louis Adit/cut above adit") was acquired sometime before 2011 and tested for gradation and Proctor density. This sample classified as sandy gravel with only 8 percent fines. The maximum dry density and optimum moisture content of this sample were 133.3 pcf and 7.5 percent, respectively, similar to the 2011 results noted above.

### 4.2 Test methods and results – 2012

Bulk samples acquired from sonic drilling samples (borings MW-202 and MW-204), and soils recovered from SPTs taken in boring CHV-101S were tested for gradation and plasticity. The results of the laboratory testing are included in Table 4.1; laboratory data sheets for this testing are provided in Appendix B.

The moisture content of the near-surface fill ranged from 12 to 18 percent; and in the underlying native colluvium generally 8 to 18 percent (up to 36 percent at 25 feet depth in MW-202). Samples of the smaller gravel (i.e.,  $\frac{3}{4}$ -1 inch minus) through fines fraction of the colluvium recovered from Standard Penetration Tests (SPT) in CHV-101S and sonic cores from two other borings (MW-202 and MW-204) classify as non- to very slightly plastic, silty to locally very slightly clayey sand and gravel. Fines in these samples ranged from 2.6 to 29.6 percent, with an average of 13.7 percent (and only 2 of 17 samples less than about 8 percent).



## 5.0 Site Characterization

This section of the report describes the condition of the St. Louis Tunnel, the local geologic setting, the characteristics of the geologic units present, and groundwater conditions in the area relevant to the hydraulic control measures under consideration as documented in the Preliminary Design Report, St. Louis Tunnel Hydraulic Control Measures (Atlantic Richfield Company, 2013b).

### 5.1 St. Louis tunnel

The investigations documented in this report focused on the portion of the SLT that was originally driven through approximately 330 feet of colluvium at the base of CHC Hill, and then into bedrock of the Hermosa Formation to just beyond the reach that was reportedly lagged (i.e., approximately 35 feet into the rock from the contact with colluvium). Based on archival tunnel geologic mapping and historic photographs, it is inferred that the tunnel is nominally seven (7) feet high and nine (9) feet wide. It is important to note, however, that these are nominal dimensions and the actual width and especially the height could vary significantly (up to at least a foot or more depending on over-breaks, support installation, and possible local over-excavations).

Available aerial photographs show that a major excavation was made over the downgradient reach of the SLT sometime between August 1950 and October 1952. It is speculated that this was to reduce the overburden stress on the timber supports in the colluvial section of the tunnel and reduce what was likely a frequent need to repair or replace support (based on anecdotal discussion in McKnight, 1974). The resultant steeply sloping U-shaped excavation is now referred to as the “terrain trap”. The slopes in this area are excessively steep and judged at best metastable to unstable near surface at their angle of repose. Cobble- and boulder-size rocks roll and tumble down these slopes, especially following rainfall and snowmelt events. Finer (sand and gravel fraction) colluvium also continues to be transported down slope by gravity, accumulating at the toes of the slopes. It has been observed that approximately 2-4 feet of colluvial debris (including cobbles and boulders) have accumulated behind a 4-foot high “jersey barrier” wall placed in the terrain trap in October 2011.

Review of subsequent aerial photography is interpreted to show that the remaining ground over this reach of the tunnel remained relatively undisturbed until at least August 1989, except that raveling of the slopes removed the benches visible shortly after the initial excavation. An informal discussion with one of the Anaconda Minerals Company mining engineers as reported by Sandy Riese (Personal communication, 2013) confirmed that the portion of the tunnel through the colluvial section was in good condition with adequate timber support as late as approximately 1985. Sometime later, inferred by review of available aerial photography as before September 1998, it appears that someone borrowed the remaining colluvial cover over the first approximately 250 feet of the tunnel in-by the original portal location. In this reach, the back (i.e., the roof) of the tunnel is now mostly gone and the tunnel is partially filled with damaged and displaced timber supports and what is assumed to be displaced colluvium ranging from silty sand to cobbles and boulders. The upper end of the now “open, collapsed” portion of the tunnel is blocked by a boulder at least seven (7) feet in visible dimension and water currently begins emerging at the surface at this point. It is inferred that the next approximately 60 feet of the tunnel upgradient in the colluvial section is at least partially plugged with displaced colluvium and broken timber supports. This inference is based primarily on the observation that boring AT-2 appears to have penetrated the tunnel in a relatively open reach, but encountered water filling the tunnel to the back. Without a leaky blockage, the average tunnel flows would be on the order of well less than a foot deep above the tunnel floor. This reach, estimated to be up to approximately 70 feet long, is referred to as the “debris plug”. It is not known if there is additional debris plugging some or all of the remaining

October 2013



approximately 60 feet of the tunnel in the colluvial reach to the contact with Hermosa Formation bedrock.

## **5.2 Site geology**

An interpretation of the geologic conditions in the vicinity of the St. Louis Tunnel portal and adit collapse area is shown in plan on Figure 5.1 and in profile along the St. Louis tunnel centerline on Figure 5.2. This interpretation is based on surface geologic mapping of the slope conditions located upslope and in the vicinity of the tunnel alignment and the results of the exploratory drilling, test pitting, and surface geophysical surveying completed to date (see Figure 3.1 for locations of exploratory features). An exposure of bedrock consisting of the Lower Hermosa Formation was mapped several hundred feet upslope of the tunnel portal area. The bedrock in this exposure consists of a bedded sequence of sandstone and siltstone defined by both outcrops and subcrops (areas where the material has broken off or is derived from in-place outcrops but probably not moved more than a few feet from its original location) and therefore marks the approximate location of intact bedrock at the ground surface above the tunnel.

There is also a small localized active landslide located in the slope above the collapsed tunnel entrance area. The surface expression of the slide suggests that it is shallow (<10 feet) and has not moved in the past several years. The remainder of the area located above and adjacent to the adit collapse area is covered by coarse colluvial material containing abundant boulder size blocks of displaced bedrock. As seen on Figure 5.1, the colluvium is locally covered to the north of the adit collapse area (northwest of the terrain trap) by the Soil Lead Repository constructed in 2009.

## **5.3 Geologic units**

### **5.3.1 Colluvium**

The colluvium in the vicinity of the collapsed and debris-plugged reach of the SLT is described as a heterogeneous mixture of relatively loose soil and rock ranging from predominantly non- to occasionally very slightly plastic fines (finer than the USCS No. 200 sieve), to “boulders” (typically subangular blocks of sedimentary Hermosa Formation and intrusive igneous rock) at least as large as 20 feet where visible and encountered in borings to date.

### **5.3.2 Bedrock**

Where encountered in boring BAH-01 at and just beyond the contact with colluvium, the bedrock is comprised of Hermosa Formation. In this reach, the Hermosa Formation is characterized by interbedded, fine-grained, medium greenish gray sandstone and medium dark gray siltstone that is hydrothermally altered and mineralized with finely disseminated pyrite. The approximately 25 feet of rock cored is typically moderately hard, weak to at most moderately strong, and closely fractured. Locally the bedrock sequence is cut by shear zones where the rock is closely to intensely fractured and contains clay gouge (i.e., fault gouge). A prominent quartz vein several inches thick and pockets of pyrite and quartz were also encountered. Core recovery in this reach ranged from 20 to 100 percent, averaging about 66 percent. Rock quality designation (RQD) was zero except for one 5-foot run with an RQD of 38 percent. Based on archival geologic mapping of the SLT, it appears that the quality of the bedrock likely improves approximately 35 feet beyond the colluvial contact where lagging and prominent mineralized veins are indicated as ending and “massive sandstone” is encountered.



## 6.0 References

- Atlantic Richfield Company. 2011a. *Investigations, Analyses and Evaluations (Part A - Engineering Geologic and Geotechnical Field Investigations and Laboratory Testing, Part D – Adit and Portal Investigation Report)*. Rico-Argentine Mine Site – Rico Tunnels Operable Unit OU01, Rico, Colorado; submitted to US EPA, Region 8, Denver, CO. December 30.
- Atlantic Richfield Company. 2011b. *Investigation Plan for Collapsed Adit Area at St. Louis Tunnel, Rico-Argentine Mine Site – Rico Tunnels Operable Unit OU01, Rico, Colorado*; submitted to US EPA, Region 8, Denver, CO. August 29.
- Atlantic Richfield Company. 2012. *Supplement to Investigation Plan for Collapsed Adit Area at St. Louis Tunnel, Rico-Argentine Mine Site – Rico Tunnels Operable Unit OU01, Rico, Colorado*; submitted to US EPA, Region 8, Denver, CO. July 3.
- Atlantic Richfield Company. 2013a. *Supplement to Investigation Plan for Collapsed Adit Area at St. Louis Tunnel, Rico-Argentine Mine Site – Rico Tunnels Operable Unit OU01, Rico, Colorado*; submitted to US EPA, Region 8, Denver, CO. May 31.
- Atlantic Richfield Company. 2013b. *Preliminary Design Report, St. Louis Tunnel Hydraulic Control Measures, Rico Argentine Mine Site, Rico Tunnels Operable Unit OU01, Rico, Colorado*. October 30.
- McKnight, E.T. 1974. *Geology and Ore Deposits of the Rico District, Colorado*: U.S. Geological Survey Professional Paper No. 723.
- U.S. Bureau of Reclamation. 2001. *Engineering Geology Field Manual, Second Edition, Volume II*; U.S. Department of the Interior, Bureau of Reclamation.
- U.S. Environmental Protection Agency (EPA). 2011b. *Removal Action Work Plan. Rico-Argentine Mine Site – Rico Tunnels Operable Unit OU01, Rico, Colorado*. March 9.



## Tables



Table 3.1: Groundwater Elevations

Well Completion Data  Date Measured	Location												
	AT-2	BAH-01	CHV-101D	CHV-101M	CHV-101S	CHV-101U	MW-201	MW-202	MW-203	MW-204	MW-205	MW-206	MW-207
Top Casing Elevation	8,866.2	8,912.6			8,858.9			8,859.2		8,866.0			
Bottom of Casing Elevation													
Measuring Point (MP) Elevation													
Top of Screen Elevation													
Bottom of Screen Elevation													
11/27/2012					8,822.4			DRY		8,852.1			
12/18/2012								8,824.2					
1/4/2013										8,851.6			
1/24/2013								DRY		8,851.0			
2/7/2013										8,851.3			
2/8/2013	8,859.9												
3/13/2013	8,860.0									8,850.5			
4/3/2013	8,854.4									8,850.6			
4/24/2013								8,825.6					
5/16/2013										8,850.5			
5/21/2013													
5/22/2013	8,859.4				8,810.9			8,824.5					
6/12/2013	8,859.7				8,822.7			8,824.6					
6/13/2013										8,850.4			
7/19/2013	8,859.8				8,821.7			8,826.8		8,850.6			

Notes  
All blank entries represent no data collected on that day  
All readings in feet above mean sea level



Table 4.1: Geotechnical Laboratory Testing Results

Sample Location/Type			Index Properties			Gradation			Atterberg Limits		Laboratory Compaction		Field Compaction			Direct Shear Strength		Soil Classification		
Boring/ Test Pit	Depth (ft)	Type <sup>1</sup>	Natural Moisture Content (%)	Dry Unit Weight (pcf)	Specific Gravity	Gravel > #4 (%)	Sand (%)	Fines < #200 (%)	LL (%)	PI (%)	MDD <sup>2</sup> (pcf)	OMC <sup>2</sup> (%)	DD (pcf)	MC (%)	Compaction (%)	φ' (°)	c' (psf)	Field Classification	Lab Classification	Lab Description
AT-2	No Samples Aquired																			
BAH-01	No Samples Aquired																			
CHV-101D	Testing In Progress																			
CHV-101S	2.5-4	SS	12.5	-	-	24	46.4	29.6	-	-	-	-				-	-	SC	-	
CHV-101S	5-6.5	SS	11.9	-	-	-	-	-	-	-	-	-				-	-	SC	-	
CHV-101S	7.5-9	SS	7.9	-	-	-	-	13.8	-	-	-	-				-	-	SM-GM	-	
CHV-101S	10-11.5	SS	8.8	-	-	-	-	-	-	-	-	-				-	-	SM-GM	-	
CHV-101S	12.5-14	SS	14.9	-	-	40	42.6	17.4	NV	NP	-	-				-	-	SC	-	
CHV-101S	15-16.5	SS	14.8	-	-	-	-	-	-	-	-	-				-	-	SC	-	
CHV-101S	17.5-19	SS	12	-	-	-	-	-	NV	NP	-	-				-	-	SC	-	
CHV-101S	20-21.5	SS	12.9	-	-	-	-	-	-	-	-	-				-	-	CL	-	
CHV-101S	22.5-23.5	SS	15.9	-	-	-	-	-	NV	NP	-	-				-	-	GC	-	
CHV-101S	27.5-29	SS	9.8	-	-	-	-	14	-	-	-	-				-	-	GM	-	
CHV-101S	30-31.5	SS	11.8	-	-	-	-	-	-	-	-	-				-	-	GC	-	
CHV-101S	45-46.5	SS	10.3	-	-	-	-	15.3	-	-	-	-				-	-	SC	-	
EW-1																				
EW-2A																				
MW-201	Testing In Progress																			
MW-202	0-1.5	SONIC	19	-	-	57	30	13	NV	NP	-	-				-	-	GM	-	
MW-202	1.5-6	SONIC	20	-	2.65	35	40	25	30	21	128	9				-	-	SC	-	Clayey Gravel With Sand
MW-202	6-9	SONIC	14.1	-	-	-	-	-	-	-	-	-				-	-	GW-GC	-	
MW-202	9-12	SONIC	18.2	-	-	-	-	-	-	-	-	-				-	-	SC	-	
MW-202	12-18	SONIC	24	-	2.65	20	70.7	9.3	30	21	125.1	10.4				-	-	SW-SM	-	Poorly graded Sand with Clay and Gravel
MW-202	18-23	SONIC	13.1	-	2.65	20	70.7	9.3	30	21	125.1	10.4				-	-	SW-SM	-	Poorly graded Sand with Clay and Gravel
MW-202	23-30	SONIC	36	-	2.65	20	70.7	9.3	30	21	125.1	10.4				-	-	SW-SM	-	Poorly graded Sand with Clay and Gravel
MW-202	30-35.5	SONIC	9.7	-	-	-	-	-	-	-	-	-				-	-	SW-SM	-	
MW-203	Testing In Progress																			
MW-204	0-7	SONIC	7.9	-	2.65	74	23	3	-	-	125.9	9.9				-	-	GW	-	
MW-204	7-10.5	SONIC	9.7	-	2.65	-	-	-	29	10	125.9	9.9				-	-	GW-GC	-	
MW-204	10.5-12	SONIC	9.4	-	2.65	67	30.4	2.6	-	-	125.9	9.9				-	-	GW	-	
MW-204	12-15	SONIC	14.4	-	2.65	-	-	-	29	10	125.9	9.9				-	-	GW-GC	-	
MW-204	21-25.5	SONIC	16.6	-	2.65	54	38.4	7.6	-	-	125.9	9.9				-	-	GW-GM	-	
MW-205	Testing In Progress																			
MW-206	Testing In Progress																			
MW-207	Testing In Progress																			
SSR-103																				
St. Louis Adit	Out Above Ad	BULK	-	-	-	49	43	8	-	-	133.3	7.5				-	-	-	-	
TP-2004A																				
TP-2004B																				
TP2011-AT1	0-2	BULK	-	-	2.65	32	45	23	24	6	127.2	9.2	97.5	12.8	77	-	-	-	SC-SM	Silty Clayey Sand With Gravel
TP2011-AT2	0-2	BULK	-	-	2.65	46	37	17	21	NP	138	7.6	100.8	11.7	73	-	-	-	GM	Silty Gravel With Sand
TP2011-AT3	0-2	BULK	-	-	2.65	49	38	13	-	-	135.6	8.2				-	-	-	GM	Silty Gravel With Sand
TP2011-AT4	No Samples Aquired																			
TP2011-AT5	0-2	BULK	-	-	2.65	50	31	19	35	8	133.4	8.4	118.0	15.8	88	-	-	-	GM	Silty Gravel With Sand
TP2011-AT6	0-2	BULK	-	-	2.65	40	38	22	32	11	130.1	9.3	109.3	14.8	84	-	-	-	GC	Clayey Gravel With Sand
TP2011-17																				
TP-17																				
TP-18																				
TP-22																				
TP2013-6	Testing In Progress																			



Table 4.1: Geotechnical Laboratory Testing Results

Sample Location/Type			Index Properties			Gradation			Atterberg Limits		Laboratory Compaction		Field Compaction			Direct Shear Strength		Soil Classification		
Boring/ Test Pit	Depth (ft)	Type <sup>1</sup>	Natural Moisture Content (%)	Dry Unit Weight (pcf)	Specific Gravity	Gravel > #4 (%)	Sand (%)	Fines < #200 (%)	LL (%)	PI (%)	MDD <sup>2</sup> (pcf)	OMC <sup>2</sup> (%)	DD (pcf)	MC (%)	Compaction (%)	φ' (°)	c' (psf)	Field Classification	Lab Classification	Lab Description
TP2013-7	Testing In Progress																			
TP2013-8	Testing In Progress																			



**Notes:**  
<sup>1</sup>SS - Split spoon; SONIC - Sonic core; BULK - Composite grab sample  
<sup>2</sup>Maximum Dry Density (MDD) and Optimum Moisture Content (OMC) per ASTM D698, unless otherwise noted.  
<sup>3</sup>Tested per ASTM D1557



## Figures

October 2013





# ADIT AND PORTAL INVESTIGATION REPORT – 2013 UPDATE


## AECOM

SITE MAP  
FIGURE 1.1










# ADIT AND PORTAL INVESTIGATION REPORT - 2013 UPDATE

## 2013 SURVEY OF COLLAPSED ADIT AREA

FIGURE 2.2




File name: Z:\CURRENT PROJECTS\ATLANTIC RICHFIELD\017577\RIC000\03 CAD\DWG\EXHIBITS\2013\2013-APR-FIGURE\2013-APR-FIG-3.1\_ADT-PLAN.PIC, 03D-2013.DWG, Last saved by: RODENA, Last Plotted: 10/30/2013 8:35 AM, Project Management Initials, Designer, Checker, Approved, ANSIB 11" x 17"













## **Appendix A: Field Investigations**

- 1. Boring Logs, Core Photographs, and Well Completion Diagrams**
- 2. Test Pits**
- 3. Surface Geophysical Surveys**



## **1. Boring Logs, Core Photographs, and Well Completion Diagrams**


AT-02  
BAH-01  
CHI-101  
CHI-102A  
CHI-102B  
CHI-102C  
CHI-103  
CHV-101D  
CHV-101M  
CHV-101S  
CHV-101U  
DG-1  
DG-3  
EW-1  
EW-2A  
MW-201  
MW-202  
MW-203  
MW-204  
MW-205  
MW-206  
MW-207  
SSR-103



AECOM LOG 60157757.GPJ FS\_DATATEMPLATE.GDT 12/13/11

		CLIENT <b>Atlantic Richfield Company</b>			LOG OF BORING NUMBER <b>AT-2</b>				
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>			ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>				
SITE LOCATION								<div style="text-align: center;"> </div>	
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE	RECOVERY	DESCRIPTION OF MATERIAL				
X					SURFACE ELEVATION    +8,866.2 Feet				
5.0						Talus slope wash, colluvium, boulders up to 8.0' diameter visible on surface			
10.0									
15.0					13.0	VOID - Drill stem advanced with no down pressure			
					16.0	Colluvium			
20.0					19.0	Encountered tunnel at 19.0' at a 32 degree angle boring. Drill stem advanced under very little down pressure.			
25.0					25.0	Encountered railroad rail, tie and ballast rock from 25.0-26.5' in core barrel - Possible Bedrock			
					26.5	Trip out change to HQ core.			
30.0					Continue as rock log below 25.0'.				
35.0									
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.									
NORTHING <b>1389126</b>					BORING STARTED			AECOM OFFICE <b>Denver</b>	
EASTING <b>2268406</b>					BORING COMPLETED			ENTERED BY <b>KKB</b>	
WL					RIG/FOREMAN <b>/</b>			SHEET NO. <b>1</b> OF <b>1</b>	
								AECOM JOB NO. <b>60157757</b>	



		CLIENT <b>Atlantic Richfield Company</b>				LOG OF BORING NUMBER <b>AT-2</b>										
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>				ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>										
SITE LOCATION						SURFACE ELEVATION <b>+8,866.2 Feet</b>										
<div style="border: 1px solid black; padding: 2px;"> <div style="border: 1px solid black; width: 10px; height: 10px; margin: 0 auto;"></div> </div>	DEPTH(FT) ELEVATION(FT)	DRILLING				LITHOLOGY		DISCONTINUITY								
		RUN NO.	CORING TIME, MIN/FT (AVG)	RECOVERY, %	ROD, %	GRAPHIC	VISUAL DESCRIPTION AND REMARKS	FRACTURE FREQUENCY (BREAK/FT)	DEPTH, FT	DIP, DEG	TYPE	APERTURE	INFILL	AMOUNT	SHAPE	ROUGHNESS
						Rock core log continued from soil boring log at 25.0'										
	25.0	Run No.				25										
		Run No.				26.5	Encountered railroad rail, tie and ballast rock in core barrel									
							Bedrock or rock present from 26.5-35.0', Latite porphyry (intrusive rock)									
	30.0	Run No.					No significant recovery									
	35.0					35	End of boring at 35.0' (drilled at 32 degrees horizontal) Core logged by : L. Beem T.O. Casing EL. 8866.21									
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.																
NORTHING <b>1389126</b>						BORING STARTED				AECOM OFFICE <b>Denver</b>						
EASTING <b>2268406</b>						BORING COMPLETED				ENTERED BY <b>KKB</b>		SHEET NO. <b>1</b> OF <b>1</b>				
WL (DEPTH)						RIG/FOREMAN <b>/</b>				APP'D BY		AECOM JOB NO. <b>60157757</b>				







AECOM LOG 60157757.GPJ FS.DATATEMPLATE.GDT 12/13/11

		CLIENT <b>Atlantic Richfield Company</b>			LOG OF BORING NUMBER <b>BAH-01</b>		
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>			ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>		
SITE LOCATION							
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE	RECOVERY	DESCRIPTION OF MATERIAL	UNIT DRY WT. LBS./FT. <sup>3</sup>	UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup> 1    2    3    4    5
							PLASTIC LIMIT %    10    20    30    40    50 WATER CONTENT %    10    20    30    40    50 LIQUID LIMIT %    10    20    30    40    50 STANDARD PENETRATION BLOWS/(FT)    10    20    30    40    50
X					SURFACE ELEVATION +8,912.6 Feet		
5.0					Cobbles, silt, sand - drilling mud: brown-red brown  Angle boring at 13 degrees from horizontal		
10.0					Easy drilling - drill mud brown		
15.0							
17.0							
20.0					17.0 Cobbles, boulders - drill mud brown with multiple rock type fragments		
25.0							
30.0					Easy drilling - drill mud brown with red ss, gray ls and others.  30.0 Boulder		
35.0					34.0 Cobbles, boulders - easy drill - drill mud brown  Moderate drill - drill mud brown		
40.0					40.0  . . . continued		


The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60157757**

SHEET NO. **1** OF **4**





AECOM LOG 60157757.GPJ FS.DATATEMPLATE.GDT 12/13/11

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>BAH-01</b>								
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>		ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>								
SITE LOCATION						<div>○ UNCONFINED COMPRESSIVE STRENGTH TONS/FT.<sup>2</sup>    1    2    3    4    5</div> <div>PLASTIC LIMIT %    WATER CONTENT %    LIQUID LIMIT % X ——— ● ——— Δ ——— 10    20    30    40    50</div> <div>⊗    STANDARD PENETRATION BLOWS/(FT) 10    20    30    40    50</div>						
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY	DESCRIPTION OF MATERIAL		UNIT DRY WT. LBS./FT. <sup>3</sup>						
⊗				SURFACE ELEVATION    +8,912.6 Feet    (Continued)								
				41.0	Boulder - moderate drill - drill mud brown Cobbles, boulders							
45.0												
50.0				50.0	Boulder - drill mud brown-red brown - multiple rock fragment types							
				53.0	Cobbles, boulders - easy drill							
55.0				55.0	Boulder							
				56.0	Cobbles, boulders - easy drill							
60.0				60.0	Boulder - drill mud brown - multiple rock fragment types							
65.0				64.0	Cobbles, boulders Lost circulation at 65.0'  Easy drill - some cobbles							
70.0												
75.0												
80.0												
					... continued							






The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.



AECOM LOG 60157757.GPJ FS.DATATEMPLATE.GDT 12/13/11


		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>BAH-01</b>								
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>		ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>								
SITE LOCATION						<div>○ UNCONFINED COMPRESSIVE STRENGTH TONS/FT.<sup>2</sup>    1    2    3    4    5</div> <div>PLASTIC LIMIT %    WATER CONTENT %    LIQUID LIMIT % X ——— ● ——— Δ ——— 10    20    30    40    50</div> <div>⊗    STANDARD PENETRATION BLOWS/(FT) 10    20    30    40    50</div>						
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE	RECOVERY	DESCRIPTION OF MATERIAL	UNIT DRY WT. LBS./FT. <sup>3</sup>						
⊗					SURFACE ELEVATION    +8,912.6 Feet    (Continued)							
	1				Cobbles, boulders							
85.0					85.0 Hard boulder - drill mud brown-red brown - multiple rock type fragments							
					88.0 Cobbles, boulders - moderate drilling							
90.0												
95.0												
100.0					Circulation 100.0-104.0' - drill mud brown-red brown							
105.0					Relatively easy drilling							
110.0												
115.0	2											
120.0					... continued							



		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>BAH-01</b>						
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>		ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>						
SITE LOCATION										
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE	RECOVERY	DESCRIPTION OF MATERIAL	UNIT DRY WT. LBS./FT. <sup>3</sup>	UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup> 1    2    3    4    5			
							PLASTIC LIMIT %    WATER CONTENT %    LIQUID LIMIT %  ---  ---  10    20    30    40    50			
SURFACE ELEVATION +8,912.6 Feet (Continued)						STANDARD PENETRATION BLOWS/(FT)				
						 10    20    30    40    50				
					Cobbles, boulders - moderate drilling					
					124.0					
125.0					Boulder - circulation restored - drill mud brown-red brown - multiple rock types in mud					
					127.0					
					Cobbles, boulders - easy drilling					
130.0										
	3									
135.0										
140.0					Boulder - circulation returns drill mud brown-red brown - multiple rock types in mud					
145.0					145.0					
					147.0					
					Drill mud changed to gray-green - mineralogy appears consistent with latite, no other rock fragments present.					
150.0					Drill mast and front of rig lift off the ground, driller backed off down pressure, rig sets back to original location. Driller notes possible bedrock at 147.0'. Drill mud appears to contain latite fragments, no others. Drilled about 6.0" into rock					
					Remove drill string 10/31/2011 (broken roller bit)					
					Replace HWT with core bit and redrill to 147.0'					
155.0					Over burden logged by L. Beem.					
					Continued as rock core log below 147.0'.					
160.0										
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.										
NORTHING <b>1388951</b>		BORING STARTED <b>10/26/11</b>		AECOM OFFICE <b>Denver</b>						
EASTING <b>2268365</b>		BORING COMPLETED <b>11/9/11</b>		ENTERED BY <b>SJH</b>		SHEET NO. <b>4</b> OF <b>4</b>				
WL		RIG/FOREMAN <b>/</b>		APP'D BY <b>EED</b>		AECOM JOB NO. <b>60157757</b>				



AECOM CORELOG 60157757.GPJ FS DATATEMPLATE.GDT 12/13/11











		CLIENT <b>Atlantic Richfield Company</b>				LOG OF BORING NUMBER <b>BAH-01</b>										
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>				ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>										
SITE LOCATION						SURFACE ELEVATION <b>+8,912.6 Feet</b>										
<div style="border: 1px solid black; padding: 2px;"> <div style="border: 1px solid black; width: 10px; height: 10px; margin: 0 auto;"></div> </div>	DEPTH(FT) ELEVATION(FT)	DRILLING				LITHOLOGY		DISCONTINUITY								
		RUN NO.	CORING TIME, MIN/FT (AVG)	RECOVERY, %	ROD, %	GRAPHIC	VISUAL DESCRIPTION AND REMARKS	FRACTURE FREQUENCY (BREAK/FT)	DEPTH, FT	DIP, DEG	TYPE	APERTURE	INFILL	AMOUNT	SHAPE	ROUGHNESS
	<b>145.0</b>	Run No.					Rock core log continued from soil boring log at 147.0'									
						147										
	<b>150.0</b>	Run No.					Cored to 153.0' - recovered few rock fragments of colluvial material. Switch back to HWT casing. No drill fluid return.									
						153										
	<b>155.0</b>	Run No.					Fragments of sandstone, shale and latite porphyry (Colluvium)									
							156.0' - Fluid returns - medium green gray									
	<b>160.0</b>	Run No.		37	20		Fragments of greenstone, quartz vein, sandstone (Colluvium) - hard - largest clast 0.8' - switch to HQ3 to sample/drill through block - angle of rods 15 degrees - core barrel stuck tripped drill string									
						163										
	<b>165.0</b>	Run No.					Variable hard and soft drilling - advanced HWT casing with shoe bit - medium brown drill fluid returns									
	<b>170.0</b>	Run No.														
	<b>175.0</b>	Run No.					174.0' - Add 10.0' feet of casing - reem/no sample									
							177.0' - Quartzite, light gray, unfractured, hard, strong - possible boulder									
	<b>180.0</b>	Run No.		62	32		177.17' - Drilling hard - return fluids change color to dark gray - switch to coring									
							Fines (matrix) wash out during drilling - cored 178.0-183.0' - hard and soft zones - returns varied light gray (hard drilling) to dark dirty									
						183										
							... continued									

The stratification lines represent the approximate boundary lines between soil/rock types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60157757**

SHEET NO.    **1**    OF    **3**





		CLIENT <b>Atlantic Richfield Company</b>				LOG OF BORING NUMBER <b>BAH-01</b>										
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>				ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>										
SITE LOCATION						SURFACE ELEVATION <b>+8,912.6 Feet</b>										
DEPTH(FT) ELEVATION(FT)	DRILLING					LITHOLOGY	DISCONTINUITY									
	RUN NO.	CORING TIME, MIN/FT (AVG)	RECOVERY, %	RQD, %	GRAPHIC		VISUAL DESCRIPTION AND REMARKS	FRACTURE FREQUENCY (BREAK/FT)	DEPTH, FT	DIP, DEG	TYPE	APERTURE	INFILL	AMOUNT	SHAPE	ROUGHNESS
 185.0	Run No.					186	brown (soft drilling) "Soft" smooth drilling no cuttings/fluid return - trip HQ rods advance HWT casing through colluvium, no returns 185.42' - Drilling becomes hard, switch to HQ3 core									
	Run No.		98	60		190	Sandstone, light green gray, massive, hard, moderately strong, fine grained 189.17' - Dark gray siltstone, closely fractured, moderately hard, weak, grades to s.s.									
190.0	Run No.		80	40		190.5	Medium dark gray limestone closely fractured  Drill/core to 193.0' and pull drill string									
	Run No.		41	12		200	Sandstone and siltstone with medium brown sandy clay matrix - variable hard to soft drilling - most fines (matrix) washing out 193.42' - Drilling becomes variably hard, soft zones encountered 198-58' - Latite porphyry - light green gray, medium grained with pyrite stringers to veinlets									
195.0	Run No.		78	20		205	No circulation Wash out from 200.0-202.33' 202.33' - Latite porphyry, medium bluish gray (5B 5/1), hard, moderately strong with feldspars to 0.25"									
	Run No.		76	0		209.58	204.5' - Shale, medium to dark gray (N3.5), hard, weak, closely fractured.  Colluvium consists of mixture of sandstone, shale, arkose with red siltstone									
200.0	Run No.		82	20			Fine grained matrix wash out - clast range from 0.4'-0.5" Altered sandstone - medium greenish gray, fine grained, with apparent relic beds or cross bed at 25 degrees to axis of core - moderately fractured, moderately hard, weak with pyrite and quartz along fracture surfaces (up to 0.25")									
	Run No.		67	0		220.5	214.5' - Small fault zone Possible bedrock at 215.0' Closely fractured									
205.0	Run No.		77	0			... continued									
210.0																
215.0																
220.0																

The stratification lines represent the approximate boundary lines between soil/rock types: in situ, the transition may be gradual.

AECOM JOB NO. **60157757**     SHEET NO. **2** OF **3**



		CLIENT <b>Atlantic Richfield Company</b>				LOG OF BORING NUMBER <b>BAH-01</b>										
		PROJECT NAME <b>Rico-Argentine Site - OU01</b>				ARCHITECT-ENGINEER <b>Drilling Company: Boart Longyear</b>										
SITE LOCATION						SURFACE ELEVATION <b>+8,912.6 Feet</b>										
DEPTH(FT) ELEVATION(FT)		DRILLING			LITHOLOGY			DISCONTINUITY								
<input type="checkbox"/>		RUN NO.	CORING TIME, MIN/FT (AVG)	RECOVERY, %	RQD, %	GRAPHIC	VISUAL DESCRIPTION AND REMARKS	FRACTURE FREQUENCY (BREAK/FT)	DEPTH, FT	DIP, DEG	TYPE	APERTURE	INFILL	AMOUNT	SHAPE	ROUGHNESS
<b>225.0</b>		Run No.		100	38		224.25 Shear zone - siltstone dark green gray, closely fractured with light gray gouge along fractures. Loss circulation, core blocked, stop trip at 220.5' - switch back to 5.0' core barrel for recovery Good circulation through 5.0' run - NQ rods at 15.5 to horizontal degrees at surface									
<b>230.0</b>							230 Siltstone, medium dark gray (N3.5), hydrothermally alt., finely dissim. pyrite, closely fractured with quartz veins and veinlets 0.063-.125" , moderately hard, weak to moderate;y strong.									
<b>235.0</b>							235.2 Quartz vein, white to light gray (N9-N7), with vugs Lost circulation									
<b>240.0</b>							240 Sandstone/siltstone, medium dark gray (N4/5), sandstone very fine grained grades at 238.0' to siltstone, closely fractured, moderately hard, weak with pockets of pyrite and quartz to 0.25"									
<b>245.0</b>							240.0-252.0' - VOID - pushed rods with no resistance except for apparent slough zone when lowered rods to 244.0' to advance another 5.0'. Pushed back through void from 246.0-252.0'. Assume one continuous void (St. Louis Tunnel)									
<b>250.0</b>		Run No.					252 Drill stem appeared to be following tunnel; at risk of losing core barrel terminated drilling hole after 12.0' of void.									
<b>255.0</b>																
<b>260.0</b>																
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.																
NORTHING <b>1388951</b>						BORING STARTED <b>10/26/11</b>				AECOM OFFICE <b>Denver</b>						
EASTING <b>2268365</b>						BORING COMPLETED <b>11/9/11</b>				ENTERED BY <b>SJH</b>		SHEET NO. <b>3</b> OF <b>3</b>				
WL (DEPTH)						RIG/FOREMAN <b>/</b>				APP'D BY <b>EED</b>		AECOM JOB NO. <b>60157757</b>				



[illegible]



AECOM LOG 60239818 RICO-UPDATED 4-8-13.GPJ FS.DATATEMPLATE.GDT 4/29/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>CHI1-102(B)</b>		
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>		
SITE LOCATION <b>Rico-Argentine</b>				<div style="display: flex; justify-content: space-between;"> <div>             UNCONFINED COMPRESSIVE STRENGTH              TONS/FT.<sup>2</sup>    1    2    3    4    5           </div> <div>             PLASTIC LIMIT %    WATER CONTENT %    LIQUID LIMIT %                        10    20    30    40    50           </div> </div> <div style="display: flex; justify-content: space-between;"> <div>             STANDARD PENETRATION    BLOWS/(FT)                    10    20    30    40    50           </div> </div>		
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY			DESCRIPTION OF MATERIAL
SURFACE ELEVATION    Feet    (Continued)						
35.0		HW		<p>Mixture of soil and rock fragments are predominantly 1/2 red brown fine grained sandstone, 1/2 bluish green altered quartzite with finely diss py; rock set in red brown sandy silt soil</p> <p>Hard zone noted at 33.0 ft</p>		
40.0		HW				
45.0		HW				
50.0		HW		47.5 Boulder		
55.0		HW		51.5 Mixture of soil and rock fragments are predominantly 1/2 red brown fine grained sandstone, 1/2 bluish green altered quartzite with finely diss py; rock set in red brown sandy silt soil		
60.0		HW		... continued		

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **2** OF **3**







AECOM LOG 60239818 RICO-UPDATED 10-11-13.GPJ FS.DATATEMPLATE.GDT 10/15/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>CHV-101D</b>	
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>	
SITE LOCATION <b>Rico-Argentine</b>					
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY	DESCRIPTION OF MATERIAL	UNIT DRY WT. LBS./FT. <sup>3</sup>
SURFACE ELEVATION Feet					
5.0	1	SON	8.0	Colluvium - 0% boulder, 5% cobble, 55% gravel, 10% coarse sand, 10% medium sand, 10% fine sand, 10% fines, 0% organics - 5YR 4/3  Cobbles from 4.0 to 5.0 feet	10
10.0			15.0	Colluvium - 0% boulder, 2% cobble, 50% gravel, 11% coarse sand, 11% medium sand, 11% fine sand, 15% fines, 0% organics - 10 YR 4/3 Perched water at 9.0 feet  Water Test at 11.0 feet	20
20.0		2A	25.0	Colluvium - 0% boulder, 2% cobble, 50% gravel, 14% coarse sand, 13% medium sand, 13% fine sand, 8% fines, 7% organics - 5 YR 4/4 Water Test at 20.0 feet Color becomes 10 YR 4/4 Cobbles form 23.0 to 29.0 feet	30
25.0			30.0	Perched water at 29.0 feet Water Test at 29.5 feet	40
		2B		... continued	50

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **1** OF **5**



<b>AECOM</b>		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>CHV-101D</b>					
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>					
SITE LOCATION <b>Rico-Argentine</b>									
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY	DESCRIPTION OF MATERIAL				UNIT DRY WT. LBS./FT. <sup>3</sup>	UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup> 1 2 3 4 5
									PLASTIC LIMIT % X --- -- ● --- -- △
									WATER CONTENT % 10 20 30 40 50
									LIQUID LIMIT % 10 20 30 40 50
				(Continued)					STANDARD PENETRATION BLOWS/(FT) 10 20 30 40 50
				SURFACE ELEVATION Feet					
				Colluvium - 0% boulder, 2% cobble, 50% gravel, 14% coarse sand, 13% medium sand, 13% fine sand, 8% fines, 7% organics - 5 YR 4/4					
				33.0					
				Colluvium - 0% boulder, 5% cobble, 50% gravel, 14% coarse sand, 13% medium sand, 13% fine sand, 8% fines, 0% organics - 10YR 4/4					
				Perched water at 35.0 feet					
				Color becomes 7.5 YR 2.5/5 Fines drop to 5% Significant black carbon content					
				40.0					
				Water Test at 40.0 feet					
				41.0					
				Alluvial/Colluvium - 0% boulder, 2% cobble, 50% gravel, 12% coarse sand, 12% medium sand, 12% fine sand, 12% fines, 0% organics - 10YR 4/4					
				Water at 44.0 feet (saturated zone)					
				45.0					
				50.0					
				Alluvial/Colluvium - 0% boulder, 2% cobble, 50% gravel, 14% coarse sand, 13% medium sand, 13% fine sand, 8% fines, 0% organics - 5 YR 4/4 Water Test at 50.0 feet					
				55.0					
				60.0					
				... continued					

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO. 60239818      SHEET NO. 2 OF 5











[illegible]



AECOM LOG 60239818 RICO-UPDATED 10-11-13.GPJ FS\_DATATEMPLATE.GDT 10/15/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>CHV-101D</b>							
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>							
SITE LOCATION <b>Rico-Argentine</b>											
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE								
DESCRIPTION OF MATERIAL											
SURFACE ELEVATION Feet (Continued)											
	11	SON		<p>Severely weathered boulders/cobbles - ?% boulder, 10% cobble, 70% gravel, 10% coarse sand, 5% medium sand, 5% fine sand, 2% fines, 0% organics - 1 GLEY 4/1</p> <p>Water Test at 120.0 feet</p> <p>Residual low plasticity silt from weathered boulder 1 GLEY 3/N calcareous and non-calcareous hard sandstone cobbles and gravels, weathered mud stone, scattered chunks of hard recemented fault gouge with unoxidized pyrite mineralization, no residual soils returned from 132.0 to 135.0 feet, could be due to wet core method</p>	<p>UNIT DRY WT. LBS./FT.<sup>3</sup></p>						
125.0											
130.0											
135.0											
140.0				140.0	<p>Very thin to thinly laminated significant sandstones to mud stones, significant pyrite mineralization along bedding planes, bedding planes on intact core fragmentation oriented near horizontal</p>						
					<p>Uncemented fault gouge with 1 GLEY 2.5/N non-calc siltstone chunks in low to moderate plastic, 1 GLEY 2.5/N silt (ML) matrix</p>						
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.											
NORTHING		BORING STARTED		AECOM OFFICE <b>Denver</b>							
EASTING		BORING COMPLETED		ENTERED BY <b>CAH</b>							
WL		RIG/FOREMAN <b>Boart/Longyear Sonic 300/Rick Mallet</b>		SHEET NO. <b>5</b> OF <b>5</b>							
				AECOM JOB NO. <b>60239818</b>							


































































AECOM LOG 60239818 RICO-UPDATED 10-11-13.GPJ FS.DATATEMPLATE.GDT 10/21/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>CHV-101M</b>		
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>		
SITE LOCATION <b>Rico-Argentine</b>						
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE	RECOVERY	DESCRIPTION OF MATERIAL	
					SURFACE ELEVATION    Feet	
5.0						
10.0						
15.0						
20.0						
25.0						
30.0						
						... continued
<div>The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.</div> <div><div>AECOM JOB NO. <b>60239818</b></div><div>SHEET NO. <b>1</b> OF <b>2</b></div></div>						

UNCONFINED COMPRESSIVE STRENGTH  
TONS/FT.<sup>2</sup>  
1    2    3    4    5

PLASTIC LIMIT %    WATER CONTENT %    LIQUID LIMIT %  
X    ●    △  
10    20    30    40    50

STANDARD PENETRATION BLOWS/(FT)  
10    20    30    40    50



[illegible]



AECOM LOG 60239818 RICO-UPDATED 4-8-13.GPJ FS.DATATEMPLATE.GDT 4/29/13

<div>AECOM</div>		CLIENT		LOG OF BORING NUMBER		CHV-101S (MW)	
		Atlantic Richfield Company		DRAFT			
PROJECT NAME		Rico - Argentine Mine Site		ARCHITECT-ENGINEER		Anderson Engineering Company, Inc.	
SITE LOCATION				Rico-Argentine			
DEPTH(FT)				ELEVATION(FT)			
SAMPLE NO.				SAMPLE TYPE			
SAMPLE DISTANCE				RECOVERY			
DESCRIPTION OF MATERIAL				UNIT DRY WT.			
SURFACE ELEVATION +8,858.9 Feet				LBS./FT. <sup>3</sup>			
<div><div><div><div><div>1</div><div>2</div><div>3</div><div>4</div><div>5</div></div><div>UNCONFINED COMPRESSIVE STRENGTH TONS/FT.<sup>2</sup></div></div><div><div><div>10</div><div>20</div><div>30</div><div>40</div><div>50</div></div><div>PLASTIC LIMIT %</div></div><div><div><div>10</div><div>20</div><div>30</div><div>40</div><div>50</div></div><div>WATER CONTENT %</div></div><div><div><div>10</div><div>20</div><div>30</div><div>40</div><div>50</div></div><div>LIQUID LIMIT %</div></div><div><div><div>10</div><div>20</div><div>30</div><div>40</div><div>50</div></div><div>STANDARD PENETRATION BLOWS/(FT)</div></div></div></div>							
1 AS							
2 SS							
5.0 HSA							
3 SS							
HSA							
7.5							
4 SS							
10.0 HSA							
5 SS							
HSA							
12.0							
6 SS							
15.0 HSA							
7 SS							
HSA							
8 SS							
20.0 HSA							
9 SS							
HSA							
22.5							
10 SS							
25.0 HSA							
11 SS							
HSA							
27.5							
12 SS							
29.0							
30.0 HSA							
29.7							
Boulder							
... continued				* Calibrated Penetrometer			

6

8

21

20

13

15

16


13

33

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
60239818

SHEET NO. 1 OF 2







The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **1** OF **2**



		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>CHV-101S (MW)</b>	
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>	
SITE LOCATION <b>Rico-Argentine</b>				  	
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY		
SURFACE ELEVATION +8,858.9 Feet (Continued)					
35.0	13	SS		Clayey gravel, some fine to coarse sand - brown 10YR5/3 - dense - wet (GC)	
				32.0 Boulders and Cobbles	
				35.0 Cobbles, gravel, and sand	
				37.0 Gravel	
				38.0 Cobbles	
40.0		HSA		40.0 Gravel and cobbles	
				41.0 Cobbles	
				42.0 Gravel and Cobbles	
45.0				44.0 Well graded silty gravel and fine to coarse sand, trace clay, with seams of clayey gravelly sand - 15% fines - brown 10YR4/3 - very dense - wet (GM) - with seams of clayey sand (SC)	
	14	SS			
		HSA			
48.0					
				* Calibrated Penetrometer	
Drilled with 4-1/4" ID HSA to 29 feet. Auger refusal at 29 feet due to boulder. Offset 6' east and blank drilled to 30 feet. Offset boring advanced to 48 feet with 4-1/4" HSA with auger refusal at 48 feet. Piezometer installed in borehole with tip at 48 feet.					
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.					
NORTHING <b>1389079.288</b>		BORING STARTED <b>11/1/12</b>		AECOM OFFICE <b>Denver</b>	
EASTING <b>2268257.515</b>		BORING COMPLETED <b>11/2/12</b>		ENTERED BY <b>AMH</b>	
WL <b>W.L. @ 27.1 W.S.</b>		RIG/FOREMAN <b>CME 85/Rory Pilmore</b>		SHEET NO. <b>2</b> OF <b>2</b>	
				AECOM JOB NO. <b>60239818</b>	



Route To: Watershed/Wastewater ☐ Waste Management ☐  
Remediation/Redevelopment ☐ Other ☐

Page 1 of 2

Facility/Project Name <b>St. Louis Ponds Area, Rico, Colorado</b>		License/Permit/Monitoring Number <b>AARCOE0105.00</b>		Boring Number <b>EW-1</b>	
Boring Drilled By: Name of crew chief (first, last) and Firm <b>Jeff Pennell Layne-Western</b>		Date Drilling Started <b>11/20/2004</b>		Date Drilling Completed <b>11/21/2004</b>	
Drilling Method <b>odex</b>					
WI Unique Well No.	DNR Well ID No.	Common Well Name <b>EW-1</b>		Final Static Water Level Feet Site	Surface Elevation <b>8,850.5 Feet Site</b>
				Borehole Diameter <b>5.0 inches</b>	
Local Grid Origin <input checked="" type="checkbox"/> (estimated: <input type="checkbox"/> ) or Boring Location <input type="checkbox"/>		State Plane <b>N, E S/C/N</b>		Local Grid Location <input checked="" type="checkbox"/> N <input checked="" type="checkbox"/> E	
NW 1/4 of NW 1/4 of Section <b>25, T 40 N, R 10 W</b>		Lat _____ ° _____ ' _____ "		Long _____ ° _____ ' _____ "	
Facility ID		County	County Code	Civil Town/City/ or Village <b>Rico, Colorado</b>	

Sample		Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments
Number and Type	Length Att. & Recovered (in)								Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	
1 SS	24	17-20 15-11	2	FILL: Brown, dense, GRAVELLY SAND, some organics in surface soils.					35					Note: Compressive Strength = SPT N value Note: Length att. on split spoon = 24"
2 SS	24	5-7 7-7	4	Brown, medium dense, fine to coarse grained CLAYEY SAND, with gravel.	SC				14					
3 SS	24	5-11 5-2	6						16					
4 SS	24	4-4 6-3	8	Brown, loose, fine to coarse grained, CLAYEY SAND.	SC				10					
5 SS	24	2-8 4-5	10	Brown, loose to very dense, fine to coarse grained, CLAYEY SAND and gravel					12					
1 SH	6	5-4	12											approx. 6 inches recovery
6 SS	24	2-4	14		SC				6					
2 SH	24		16											
7 SS	24	6-8 10-8	18						18					
8 SS	24	50	22	Brown-gray, very dense, fine-coarse GRAVEL, with sand and clay	GP				50					

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature <i>Daniel R. Reed</i>	Firm <b>SEH Inc</b>	421 Frenette Drive Chippewa Falls, WI 54729 www.sehinc.com	Tel: 715.720.6200 Fax: 715.720.6300
---------------------------------	---------------------	--	--

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.



Page 2 of 2

[illegible]



Route To: Watershed/Wastewater ☐ Waste Management ☐  
Remediation/Redevelopment ☐ Other ☐

Page 1 of 1

Facility/Project Name St. Louis Ponds Area, Rico, Colorado			License/Permit/Monitoring Number AARCOE0105.00		Boring Number EW-2A	
Boring Drilled By: Name of crew chief (first, last) and Firm Jeff Pennell Layne-Western			Date Drilling Started 11/21/2004		Date Drilling Completed 11/21/2004	
					Drilling Method odex	
WI Unique Well No.	DNR Well ID No.	Common Well Name	Final Static Water Level Feet Site	Surface Elevation 8,846.4 Feet Site		Borehole Diameter 5.0 inches
Local Grid Origin <input checked="" type="checkbox"/> (estimated: <input type="checkbox"/> ) or Boring Location <input type="checkbox"/>			Lat <input type="text"/> ° <input type="text"/> ' <input type="text"/> "		Local Grid Location	
State Plane N, E S/C/N			Long <input type="text"/> ° <input type="text"/> ' <input type="text"/> "		<input checked="" type="checkbox"/> N <input type="checkbox"/> E	
NW 1/4 of NW 1/4 of Section 25, T 40 N, R 10 W					<input type="checkbox"/> S <input type="checkbox"/> W	
Facility ID		County	County Code	Civil Town/City/ or Village Rico, Colorado		

Sample		Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	U S C S	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments
Number and Type	Length Att. & Recovered (in)								Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	
1 SS	24	1-3 12-9	2	FILL: Brown, dense, GRAVELLY SAND, some organics in surface soils.					15					Note: Compressive Strength = SPT N value Note: Length att. on split spoon = 24"
2 SS	24	3-7 4-5	4	Brown, loose, fine to coarse grained CLAYEY SAND, with gravel.	SC				11					
3 SS	24		6	Brown, loose, SANDY CLAY to clayey sand, with gravel.	CL									
4 SS	24	3-4 3-3	8	Brown, medium stiff, SANDY CLAY, with gravel	CL-MI				7					
5 SS	24	5-8 8-17	10	Brown, stiff, SANDY CLAY to clayey sand, with gravel	CL-MI				16					
			12	End of boring at 12' (abandoned)										

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature <i>Daniel R. Reed</i>	Firm <b>SEH Inc</b>	421 Frenette Drive Chippewa Falls, WI 54729 www.sehinc.com	Tel: 715.720.6200 Fax: 715.720.6300
------------------------------------	------------------------	--	--

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.



Page 2 of 2

[illegible]



AECOM LOG 60239818 RICO-UPDATED 10-11-13.GPJ FS.DATATEMPLATE.GDT 10/15/13






		CLIENT <b>Atlantic Richfield Company</b>			LOG OF BORING NUMBER <b>MW-201</b>										
		PROJECT NAME <b>Rico - Argentine Mine Site</b>			ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>										
SITE LOCATION <b>Rico-Argentine</b>															
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE	RECOVERY	DESCRIPTION OF MATERIAL					UNIT DRY WT. LBS./FT. <sup>3</sup>					
X					SURFACE ELEVATION    Feet										
5.0	1	SON			Fill - 0% boulders, 2% cobble, 50% gravel, 12% coarse sand, 12% medium sand, 14% fine sand, 10% fines, 0% organics - 7.5 YR 3/2										
10.0	2	SON			8.5	Waste Rock - 0% boulder, 0% cobble, 40% gravel, 25% coarse sand, 20% medium sand, 10% fine sand, 5% fines, 0% organics - 10 YR 5/6 0.5-inch black waste material (coal cinders) Perched water at 9.0 feet through sandy gravel layer less than 6.0 inches thick Waste Rock - 0% boulder, 2% cobble, 40% gravel, 15% coarse sand, 15% medium sand, 15% fine sand, 13% fines, 0% organics - 10 YR 3/3 Clean limestone cobble zone from 13.0-14.0 feet									
					10.0										
15.0	3	SON			15.0										
20.0	4	SON			20.0	Flood Plain Deposits - 0% boulder, 0% cobble, 30% gravel, 15% coarse sand, 15% medium sand, 15% fine sand, 25% fines, 2% organics - 5 YR 2.5/1 Perched water at 17.0 feet Root fragments Colluvium/Alluvium Mix - 0% boulder, 0% cobble, 30% gravel, 15% coarse sand, 15% medium sand, 20% fine sand, 20% fines, trace organics - 7.5 YR 3/2 Water Test at 20.0 feet									
25.0	5	SON				Jumbled chunks of black organic silt and sand at 26.0 feet  Severely weathered red sandstone gravels from 29.0 to 30.0 feet									
30.0						... continued									

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **1** OF **3**



AECOM		CLIENT Atlantic Richfield Company				LOG OF BORING NUMBER MW-201																			
		PROJECT NAME Rico - Argentine Mine Site				ARCHITECT-ENGINEER Anderson Engineering Company, Inc.																			
SITE LOCATION Rico-Argentine																									
DEPTH(FT) ELEVATION(FT) SAMPLE NO. SAMPLE TYPE SAMPLE DISTANCE RECOVERY DESCRIPTION OF MATERIAL SURFACE ELEVATION Feet (Continued)														UNIT DRY WT. LBS./FT. <sup>3</sup>	UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup> 1 2 3 4 5					PLASTIC LIMIT % WATER CONTENT % LIQUID LIMIT % 10 20 30 40 50					
																				STANDARD PENETRATION BLOWS/(FT) 10 20 30 40 50					
 30.5 Colluvium/Alluvium Mix - 0% boulder, 5% cobble, 55% gravel, 10% coarse sand, 10% medium sand, 10% fine sand, 10% fines, 0% organics - 7.5 YR 4/4 33.0																									
 35.0 7 SON Colluvium/Alluvium Mix - 0% boulder, 5% cobble, 50% gravel, 10% coarse sand, 10% medium sand, 10% fine sand, 15% fines, 0% organics - 2.5 YR 5/3 Water at 33.0 feet Grades to 7.5 YR 4/3 at 35.0 feet 37.5																									
 40.0 8 SON Limestone Cobbles - 0% boulder, 2% cobble, 55% gravel, 15% coarse sand, 10% medium sand, 10% fine sand, 8% fines, 0% organics - 7.5 YR 4/4 Water Test at 40.0 feet Grades to 7.5 YR 4/4 45.0																									
 50.0 Grades to 5 YR 4/4 50.0																									
 55.0 9 SON Alluvium - 0% boulders, 0% cobbles, 60% gravel, 10% coarse sand, 15% medium sand, 10% fine sand, 5% fines, 0% organics - 5 YR 4/4 Water Test at 50.0 feet Medium coarse sand lense from 54.5 to 55.0 feet Small coal particle - gravel-sized 60.0																									
... continued																									
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.														AECOM JOB NO. 60239818					SHEET NO. 2 OF 3						





























RICO ST. LOUIS  
INW-20  
8 OCT 13  
50 - 55  
55 - 60



AECOM LOG 60239818 RICO-UPDATED 4-8-13.GPJ FS.DATATEMPLATE.GDT 4/29/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>MW-202</b>	
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>	
SITE LOCATION <b>Rico-Argentine</b>					
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY	DESCRIPTION OF MATERIAL	<div style="display: flex; justify-content: space-between; font-size: 0.8em;"> <div>             UNCONFINED COMPRESSIVE STRENGTH TONS/FT<sup>2</sup> </div> <div>             PLASTIC LIMIT %              WATER CONTENT %              LIQUID LIMIT %           </div> </div> <div style="display: flex; justify-content: space-between; font-size: 0.8em;"> <div>             10 20 30 40 50           </div> <div>             10 20 30 40 50           </div> </div> <div style="display: flex; justify-content: space-between; font-size: 0.8em;"> <div>             STANDARD PENETRATION BLOWS/(FT)           </div> </div> <div style="display: flex; justify-content: space-between; font-size: 0.8em;"> <div>             10 20 30 40 50           </div> </div>
SURFACE ELEVATION +8,859.2 Feet					UNIT DRY WT. LBS./FT. <sup>3</sup>
	1	SON		FILL: Well graded gravel, some sand, little silt - 57% gravel, 30% sand, 13% fines - 10YR3/2 - (FILL: GM)	
5.0	2,3	SON		Clayey sand and gravel, some silt - 35% gravel, 40% fine to coarse sand, 25% fines - 7.5YR4/3 (SC)	
10.0	3,4	SON		Well graded clayey gravel and sand, little silt - 7/5YR4/3 (GW-GC)	
15.0	5	SON		Clayey sand and gravel, some silt - 35% gravel, 40% fine to coarse sand, 25% fines - 7.5YR4/3 (SC)	
20.0	6	SON		Well graded sand, some gravel, little silt - 20% gravel, 71% fine to coarse sand, 9.3% silt - 10YR4/3 (SW-SM)	
25.0	7	SON		Well graded sand, some gravel, little silt - 20% gravel, 71% fine to coarse sand, 9.3% silt - 10YR4/4 (SW-SM)	
30.0				... continued	

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **1** OF **2**



		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>MW-202</b>								
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>								
SITE LOCATION <b>Rico-Argentine</b>				<div style="text-align: center;"> </div>								
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE			RECOVERY	DESCRIPTION OF MATERIAL					
X							SURFACE ELEVATION +8,859.2 Feet (Continued)					
35.0	8	SON			Well graded sand, some gravel, little silt - 20% gravel, 71% fine to coarse sand, 9.3% silt - 10YR4/4 (SW-SM)	UNIT DRY WT. LBS./FT.³						
38.8		RB			Blind Drilling							
					End of boring at 38.8 ft. Boring advanced to 35.5 feet with sonic drilling techniques, boring advanced to 38.8 feet using mud rotary techniques. Piezometer installed with tip at 38.8 feet.							
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.												
NORTHING <b>1388999.649</b>		BORING STARTED <b>11/8/12</b>		AECOM OFFICE <b>Denver</b>								
EASTING <b>2268195.978</b>		BORING COMPLETED <b>11/11/12</b>		ENTERED BY <b>AMH</b>								
WL <b>W.L. @ 22.5' W.D.</b>		RIG/FOREMAN <b>AMS Compact Sonic 10-C/Kyle King</b>		SHEET NO. <b>2</b> OF <b>2</b>								
				AECOM JOB NO. <b>60239818</b>								



AECOM LOG 60239818 RICO-UPDATED 4-8-13.GPJ FS.DATATEMPLATE.GDT 10/14/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>MW-203</b>		
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>		
SITE LOCATION <b>Rico-Argentine</b>				<div style="text-align: center;"> </div>		
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY			DESCRIPTION OF MATERIAL
SURFACE ELEVATION    Feet						
UNIT DRY WT. LBS./FT.³						
5.0	1	SON	6.0	Colluvium - 0% cobble, 40% gravel, 15% coarse sand, 15% medium sand, 15% fine sand, 15% fines, trace organics - 7.5 YR 3/2		
10.0	2	SON	10.0	Colluvium - 2% cobble, 35% gravel, 15% coarse sand, 15% medium sand, 13% fine sand, 20% fines, 0% organics - 10 YR 4/3		
15.0	3	SON	11.5	Colluvium - 0% cobble, 30% gravel, 20% coarse sand, 20% medium sand, 20% fine sand, 10% fines, 0% organics - 10 YR 4/4 Perched water		
20.0	4	SON	21.0	4.0-inch+ cobble		
25.0	5	SON	26.0	Colluvium - 0% cobble, 40% gravel, 15% coarse sand, 15% medium sand, 15% fine sand, 15% fines, 0% organics - 7.5 YR 3/2		
30.0	6A	SON		Colluvium - 0% cobble, 50% gravel, 11% coarse sand, 12% medium sand, 12% fine sand, 15% fines, 0% organics - 10 YR 4/3		
... continued						

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **1** OF **3**



[illegible]







AECOM LOG 60239818 RICO-UPDATED 4-8-13.GPJ FS.DATATEMPLATE.GDT 4/29/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>MW-204</b>	
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>	
SITE LOCATION <b>Rico-Argentine</b>					
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY	DESCRIPTION OF MATERIAL	<div style="text-align: right; font-size: small;">             UNCONFINED COMPRESSIVE STRENGTH              TONS/FT.<sup>2</sup>    1    2    3    4    5           </div> <div style="text-align: center; font-size: x-small;">             PLASTIC    WATER    LIQUID              LIMIT %    CONTENT %    LIMIT %              X — — — — — ● — — — — — △              10    20    30    40    50           </div> <div style="text-align: center; font-size: x-small;">             STANDARD              PENETRATION    BLOWS/(FT)              ⊗    10    20    30    40    50           </div>
SURFACE ELEVATION    +8,866.0 Feet				UNIT DRY WT. LBS./FT. <sup>3</sup>	
5.0	1	SON		Well graded sandy gravel, trace silt, slightly moist - 74% gravel, 23% sand, 3% fines - 5YR3/1 (GW)	●
10.0	2	SON		7.0    Approximate top of timbers in nearby St. Louis Adit @ 6.5' Well graded sandy gravel - 50% gravel (subangular to subrounded), 35% sand, 15% fines- slightly moist to moist - 7.5YR4/3 (GW-GC) Approximate level of flowing water in adit 15'-20' away @ 8.0'. 10.5	●    X — — △
15.0	3	SON		Well graded sandy gravel, trace silt, slightly moist - 67% gravel, 30% sand, 3% fines - 10YR4/2 (GW)	●
15.0	4	SON		12.0    Well graded sandy gravel = 60% gravel (subangular to subrounded), 30% sand, 10% fines - saturated - 10YR4/4 (GW-GC) NOTE: Possible perched groundwater at 12 feet. (Approx elev. = 8854 ft) 15.0    No sampling from 15'-21' Boulders and cobbles, rough drilling, lost approximately 150 gallons of drilling mud.	●    X — — △
20.0	RB				
25.0	5	SON		21.0    Well graded sandy gravel, trace silt - 60% gravel (angular to subrounded), 25% sand, 15% fines - 5YR3/3 (GW-GM) 25.5	●
30.0	RB			No sampling from 25.5'-31.5'	
... continued					

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO.    1    OF    2







AECOM LOG 60239818 RICO-UPDATED 10-11-13.GPJ FS.DATATEMPLATE.GDT 10/15/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>MW-205</b>	
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>	
SITE LOCATION <b>Rico-Argentine</b>					
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY	DESCRIPTION OF MATERIAL	<div style="text-align: center;">  UNCONFINED COMPRESSIVE STRENGTH TONS/FT.<sup>2</sup> 1 2 3 4 5         </div> <div style="text-align: center;">           PLASTIC LIMIT %      WATER CONTENT %      LIQUID LIMIT %   ---  ---             10 20 30 40 50         </div> <div style="text-align: center;">           STANDARD PENETRATION BLOWS/(FT)   10 20 30 40 50         </div>
SURFACE ELEVATION    Feet					UNIT DRY WT. LBS./FT. <sup>3</sup>
				0.5    Topsoil	
	1	SON		Fill - 75% gravel, 22% sand, 3% fines - 10 YR 4/2	
				2.0	
	2	SON		Fill - 5% cobble, 20% gravel, 67% sand, 8% fines - 5 YR 3/2	
5.0				Large cobble	
				6.5	
	3	SON		Colluvium - 10% cobble, 40% gravel, 40% sand, 10% fines - 10YR 4/4	
10.0				Large cobble	
				14.0	
	4	SON		Colluvium - 50% gravel, 45% sand 5% fines - 5 YR 3/2	
15.0				17.5	
				25% cobble, 30% gravel, 30% sand, 15% fines - 10 YR 4/3	
20.0				Water encountered during drilling - perched	
	5A	SON			
25.0				Perched water during drilling	
				26.0	
				Colluvium - 20% cobble, 30% gravel, 40% sand, 10% fines - 10 YR 3/3	
30.0					
				... continued	

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **1** OF **6**



AECOM LOG 60239818 RICO-UPDATED 10-11-13.GPJ FS.DATATEMPLATE.GDT 10/15/13

		CLIENT <b>Atlantic Richfield Company</b>		LOG OF BORING NUMBER <b>MW-205</b>	
		PROJECT NAME <b>Rico - Argentine Mine Site</b>		ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>	
SITE LOCATION <b>Rico-Argentine</b>					
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE RECOVERY	DESCRIPTION OF MATERIAL	<div style="text-align: center;"> </div>
X				SURFACE ELEVATION    Feet    (Continued)	UNIT DRY WT. LBS./FT. <sup>3</sup>
	5B	SON		Colluvium - 20% cobble, 30% gravel, 40% sand, 10% fines - 10 YR 3/3	
35.0				35.0	
	6	SON		Colluvium - 10% cobble, 40% gravel, 45% sand, 5% fines, trace organics - 10 YR 2/2 Color change 5 YR 4/3	
				39.0	
	7	SON		Colluvium - 0% cobble, 15% gravel, 60% sand, 15% fines - 7.5 YR 3/2	
40.0				40.0	
	8	SON		Colluvium - 20% cobble, 40% gravel, 30% sand, 10% fines, trace organics - 2.5 YR 2.5/1 Significant black carbon content adhering to and staining individual particles	
				42.0	
	9	SON		Perched zone during drilling Significant black carbon content	
				44.0	
	10	SON		Colluvium - 15% cobble, 35% gravel, 40% sand, 10% fines - 5 YR 4/4 4.0-inch clayey zone Begin saturated zone 6.0-inch+ weathered sandstone cobble	
45.0				45.0	
				50.0	
	11	SON		Alluvium/Colluvium Mix - 15% cobble, 45% gravel, 25% sand, 15% fines - 7.5 YR 4/4	
50.0				50.0	
55.0					
60.0					
... continued					

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **2** OF **6**







AECOM LOG 60239818 RICO-UPDATED 10-11-13.GPJ FS.DATATEMPLATE.GDT 10/15/13

		CLIENT <b>Atlantic Richfield Company</b>			LOG OF BORING NUMBER <b>MW-205</b>		
		PROJECT NAME <b>Rico - Argentine Mine Site</b>			ARCHITECT-ENGINEER <b>Anderson Engineering Company, Inc.</b>		
SITE LOCATION <b>Rico-Argentine</b>							
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE	RECOVERY	DESCRIPTION OF MATERIAL	UNIT DRY WT. LBS./FT. <sup>3</sup>	<div style="text-align: center;">  UNCONFINED COMPRESSIVE STRENGTH TONS/FT.<sup>2</sup> 1 2 3 4 5 </div> <div style="text-align: center;">           PLASTIC LIMIT %      WATER CONTENT %      LIQUID LIMIT %   ---  ---             10 20 30 40 50 </div> <div style="text-align: center;">  STANDARD PENETRATION BLOWS/(FT)            10 20 30 40 50 </div>
X					SURFACE ELEVATION   Feet      (Continued)		
95.0	15	SON		●			
100.0				●			
102.0				●			
105.0				●			
110.0	16	SON		●			
115.0				●			
117.0				●			
120.0	17	SON		X	2.0-inch gravels - color becomes mix of 16 17  Colluvium - 0% cobble, 30% gravel, 60% sand, 10% fines - 5 YR 3/2  ... continued		

The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.

AECOM JOB NO.  
**60239818**

SHEET NO. **4** OF **6**







<div><div>AECOM</div></div>		CLIENT Atlantic Richfield Company		LOG OF BORING NUMBER MW-205						
		PROJECT NAME Rico - Argentine Mine Site		ARCHITECT-ENGINEER Anderson Engineering Company, Inc.						
SITE LOCATION Rico-Argentine				UNIT DRY WT. LBS./FT. <sup>3</sup>	UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup> 1 2 3 4 5					
DEPTH(FT) ELEVATION(FT)	SAMPLE NO.	SAMPLE TYPE	SAMPLE DISTANCE		RECOVERY	DESCRIPTION OF MATERIAL				
						SURFACE ELEVATION Feet (Continued)				
End of Boring					PLASTIC LIMIT % WATER CONTENT % LIQUID LIMIT % X --- ● --- △ 10 20 30 40 50					
					STANDARD PENETRATION BLOWS/(FT) ⊗ 10 20 30 40 50					
The stratification lines represent the approximate boundary lines between soil types: in situ, the transition may be gradual.										
NORTHING		BORING STARTED		AECOM OFFICE		Denver				
EASTING		BORING COMPLETED		ENTERED BY CAH		SHEET NO. 6 OF 6				
WL		RIG/FOREMAN Boart/Longyear Sonic 300/Rick Mallet		APP'D BY		AECOM JOB NO. 60239818				



## **2. Test Pits**

TP-2004A  
TP-2004B  
TP2011-AT1  
TP2011-AT2  
TP2011-AT3  
TP2011-AT4  
TP2011-AT5  
TP2011-AT6  
TP-17  
TP-18  
TP-22  
TP-2013XX  
TP-2013YY  
TP-2013ZZ



DEPTH (')	SAMPLE TYPE AND NUMBER	SAMPLE DEPTH INTERVAL	BLOW COUNT	RECOVERY LENGTH (%)	PROFILE	DESCRIPTION	WELL CONSTRUCTION SUMMARY
0.5						Gravel on surface, Brown sandy silt with some clay and gravel and Rock (2" to 1 1/2")	
1.0						Rock content 25%	
1.5							
2.0							
2.5							
3.0	2.7					Brown very dark silty clay with organic material, little to no rock, soil moist	
3.5							
4.0	4.0					Brown silty clay with some large rock (6" - 14")	
4.5						in 5% soil moist	
5.0							
5.5							
6.0	6.4						NO WATER ENCOUNTERED
6.5							
7.0							

## NOTES

TD=

1) Test Pit Back Filled & Compacted  
2) Sample collected, Composite of Material

AP-17








- 2.10 1) Steel pipe in trench, running N/S  
at 1.2' deep. Pipe 9"  $\Phi$   
2) Test Pit Back Filled + Compacted  
X - Sample collected, Composite of Material



TEST PIT LOG		TEST PIT #
PROJECT: <u>Rico St. Louis Ponds</u>	DATE: <u>23 OCT 13</u>	
NO: _____	LOGGED BY: <u>ACJ</u>	<u>TP2013-6</u>
WEATHER: <u>60°F, CLEAR</u>		EXCAVATION METHOD: _____
LOCATION: <u>ST. LOUIS TUNNEL AREA, BETWEEN MW-204 AND CHV-1010</u>		

Start Time: 1215 End Time: 1315 Note: \_\_\_\_\_



NOTES/SAMPLES
<p>SAMPLES:</p> <p>⑧ 0-18.5' 3.5 GAL BUCKETS</p>


SOIL TYPE	SOIL DESCRIPTION
<div>①</div> <div>⑧ SB</div>	<p>COLLUVIUM</p>



TEST PIT LOG		TEST PIT #
PROJECT: <u>Rico St. Louis Ponds</u>	DATE: <u>23 OCT 13</u>	TP <u>2013-7</u>
NO: _____	LOGGED BY: <u>ACJ</u>	
WEATHER: <u>60°F CLEAR</u>		EXCAVATION METHOD: <u>KOMATSU PC300LL</u>
LOCATION: <u>STA 0+50 ON ST. LOUIS TUNNEL COLLAPSED ABUT ACCESS</u>		

Start Time: 1330 End Time: 1430

Note: \_\_\_\_\_



#### NOTES/SAMPLES

NO PLACE TO  
STOCKPILE MATL  
LIMITS DEPTH  
TO 7.0 FEET

SAMPLES:  
⑨ 0-7.5' 3 5 GAL  
BUCKETS


SOIL TYPE	SOIL DESCRIPTION
<div style="border: 1px solid black; border-radius: 50%; width: 30px; height: 30px; display: flex; align-items: center; justify-content: center; margin: 5px;"> <div style="border: 1px solid black; border-radius: 50%; width: 15px; height: 15px; display: flex; align-items: center; justify-content: center;"> <div style="border: 1px solid black; border-radius: 50%; width: 8px; height: 8px; display: flex; align-items: center; justify-content: center;"> </div> </div> </div>	FILL, WITH OXIDIZED WASTE ROCK



TP, 2013-8

TEST PIT LOG		TEST PIT #
PROJECT: Rico St. Louis Ponds	DATE: 22 OCT 13	<del>2013</del>
NO: <del>2013-SSR-1</del>	LOGGED BY: ACJ	<del>SSR-1</del>
WEATHER: CLEAR, 40°	EXCAVATION METHOD: FIMATSU PL 300	
LOCATION: 150' EAST OF LIME PLANT BLDG		

Start Time: 1030 End Time: 1145 Note:



SOIL TYPE	SOIL DESCRIPTION (SEE ATTACHED SHEET)
<del>(A)</del>	<del>TOPSOIL</del>
<del>(2)</del>	<del>SEE S2 (FILL)</del>
<del>(3)</del>	<del>CLAYSTONE (SEE S3)</del>
	FILL (WASTE ROCK)
(S1)	FILL, WASTE ROCK, NOT OXIDIZED, SOME SCATTERED WOODY PLANT DEBRIS
(S2)	FILL, WASTE ROCK, OXIDIZED (PYRITE OXIDATION) ROCK SCATTERED



## SOIL DESCRIPTION DETAIL

**HOLE:**

~~2013-SR-1~~

SHEET 1 OF 1


[illegible]

## MATERIAL SOURCES

**F=Fill**  
**A=Alluvium**  
**AF=Alluvial Fan**  
**E=Eolian**  
**L=Landslide**  
**C=Colluvium**  
**WB=Weath Bedrk**  
**U = Unknown**

STRUCTURE (ASTM  
D2488)

STR=Stratified (Layers  
>6mm)  
LAM=Laminated  
FIS=Fissured  
SLK=Slickenside  
BLK=Blocky  
LEN=Lensed  
HOM=Homogeneous



Term	Shape
------	-------

Cylindrical \_\_\_\_\_  
Discoidal \_\_\_\_\_  
Spherical \_\_\_\_\_  
Tabular \_\_\_\_\_  
Ellipsoidal \_\_\_\_\_  
Equant \_\_\_\_\_  
Irregular \_\_\_\_\_




TABLE 12 Identification of Inorganic Fine-Grained Soils from Manual Tests

Soil Symbol	Dry Strength	Distancy	Toughness and Plasticity
ML	None to low	Slow to rapid	Low or thread cannot be formed
CL	Medium to high	None to slow	Medium
MH	Low to medium	None to slow	Low to medium
CH	High to very high	None	High




### **3. Surface Geophysical Surveys**

#### *Refraction Microtremor*


RM-201  
RM-202  
RM-203  
RM-204  
RM-205A  
RM-205B  
RM-205C



# Refraction Microtremor Line RM-201




Contours = Shear Wave Velocity (ft/sec)






# Refraction Microtremor Line RM-202






# Refraction Microtremor Line RM-203



Contours = Shear Wave Velocity (ft/sec)




# Refraction Microtremor Line RM-204



Contours = Shear Wave Velocity (ft/sec)




# Refraction Microtremor Line RM-205A



Contours = Shear Wave Velocity (ft/sec)




# Refraction Microtremor Line RM-205B





# Refraction Microtremor Line RM-205C





## **Appendix B: Geotechnical Testing**

### **Soils Testing**

- 1. Samples from Borings**
- 2. Samples from Test Pits**



## **Soils Testing**

### *1. Samples from Borings*

AT-2

BAH-01

CHV-101D

CHV-101S

EW-1

EW-2A

MW-201

MW-202

MW-203

MW-204

MW-205

MW-206

MW-207

SSR-103

St. LOUIS ADIT





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## LABORATORY REPORT

Client **ANDERSON ENGINEERING COMPANY, INC.**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Project **RICO INITIAL SOLIDS REMOVAL & DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **VARIOUS**  
Sample Source / Location **CHV-101S**  
Reference: **ASTM**  
Special Instructions:

Date of Report **12-13-12**  
Job No. **3151JM098**  
Event / Invoice No. **31520185-25** Lab No.  
Authorized By **C. SANCHEZ** Date **10-22-12**  
Sampled By **CLIENT** Date **11-02-12**  
Submitted By **J. GISSEMAN** Date **11-14-12**  
Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT** Date **10-27-12**

### TEST RESULTS

<u>ELEVATION (FT)</u>	<u>MOISTURE CONTENT (%)</u>	<u>ATTERBERGS:</u>	<u>LL</u>	<u>PL</u>	<u>PI</u>	<u>ORGANIC CONTENT (%)</u>
2.5-4'	12.5					
5-6.5'	11.9					
7.5-9'	7.9					
10-11.5'	8.8					
12.5-14'	14.9		NV	NV	NP	
15-16.5'	14.8					
17.5-19'	12.0		NV	NV	NP	
20-21.5'	12.9					
22.5-23.5'	15.9		NV	NV	NP	
27.5-29'	9.8					
30-31.5'	11.8					
45-46.5'	10.3					

Comments: **SEE ADDITIONAL PHYSICAL PROPERTIES REPORTS FOR GRADATIONS**

Copies To: **CLIENT (2)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-13-12**

Job No. **3151JM098**

Event / Invoice No. **315200185-25**

Lab No. **0981118-**

Authorized By **C. SANCHEZ**

Date **10-22-12**

Sampled By **CLIENT**

Date **11-02-12**

Submitted By **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Aggregate **VARIABLE**  
Sample Source / Location **CHV-101S 2.5-4'**  
Special Instructions: **0981118-1**

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT**

Date **11-02-12**

### TEST RESULTS

SIEVE ANALYSIS		ASTM C136	AASHTO T27	PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION					
4 IN. - 100.0				<b>UNIT WEIGHT &amp; VOIDS</b>			
3 - 75.0				FINE AGGREGATE		UNIT WEIGHT, PCF →	
2 - 50.0				<input type="checkbox"/> ASTM C29 <input type="checkbox"/> AASHTO T19		VOIDS, % →	
1 1/2 - 37.5				<input type="checkbox"/> RODDING <input type="checkbox"/> JIGGING <input type="checkbox"/> LOOSE		UNIT WEIGHT, PCF →	
1 1/4 - 31.5				COARSE AGGREGATE		VOIDS, % →	
1 - 25.0							
3/4 - 19.0	<b>100</b>			<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
1/2 - 12.5	<b>95</b>			FINE AGGREGATE		BULK SPECIFIC GRAVITY →	
3/8 - 9.5	<b>86</b>			<input type="checkbox"/> ASTM C128 <input type="checkbox"/> AASHTO T84		BULK SPECIFIC GRAVITY (SSD) →	
1/4 - 6.3	<b>81</b>			AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
NO. 4 - 4.75	<b>76</b>			<input type="checkbox"/> YES <input type="checkbox"/> NO		ABSORPTION, % →	
8 - 2.36	<b>67</b>			COARSE AGGREGATE		BULK SPECIFIC GRAVITY →	
10 - 2.00	<b>65</b>			<input type="checkbox"/> ASTM C127 <input type="checkbox"/> AASHTO T85		BULK SPECIFIC GRAVITY (SSD) →	
16 - 1.18	<b>60</b>			AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
30 - .600	<b>52</b>			<input type="checkbox"/> YES <input type="checkbox"/> NO		ABSORPTION, % →	
40 - .425	<b>49</b>						
50 - .300	<b>45</b>			<b>SAND EQUIVALENT VALUE</b>			
100 - .150	<b>36</b>			<input type="checkbox"/> ASTM D2419 <input type="checkbox"/> AASHTO T176		% →	
<b>FINER THAN NO. 200</b>				<b>RESISTANCE TO DEGRADATION</b>			
<input checked="" type="checkbox"/> ASTM C117		<b>29.6</b>		SMALL COARSE AGGREGATE		100 REV., % LOSS →	
<input type="checkbox"/> AASHTO T11				<input type="checkbox"/> ASTM C131 <input type="checkbox"/> AASHTO T96		500 REV., % LOSS →	
				GRADING			
				LARGE COARSE AGGREGATE		200 REV., % LOSS →	
				<input type="checkbox"/> ASTM C535		1000 REV., % LOSS →	
				GRADING			
<b>FINENESS MODULUS, ASTM C125 →</b>				<b>LIGHTWEIGHT PIECES</b>			
				<input type="checkbox"/> ASTM C123 <input type="checkbox"/> AASHTO T113		FINE AGGREGATE, % →	
						COARSE AGGREGATE, % →	
<b>LIQUID &amp; PLASTIC PROPERTIES</b>				<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>			
<input type="checkbox"/> ASTM D4318 <input type="checkbox"/> AASHTO T89 & T90				<input type="checkbox"/> ASTM C142 <input type="checkbox"/> AASHTO T112		FINE AGGREGATE, % →	
METHOD <input type="checkbox"/> A <input type="checkbox"/> B		RESULT		SPECIFICATION		COARSE AGGREGATE, % →	
LIQUID LIMIT							
PLASTIC LIMIT							
PLASTICITY INDEX							
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO				<b>FRACTURED FACES</b>			
				COARSE AGGREGATE BY WEIGHT		ONE OR MORE FACES, % →	
				<input type="checkbox"/> ASTM D5821 <input type="checkbox"/> FLH T507 <input type="checkbox"/> FAA <input type="checkbox"/>		TWO OR MORE FACES, % →	
<b>CLEANNES VALUE</b>		<b>CA227 →</b>		<b>DURABILITY INDEX</b>			
				<input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210		D <sub>c</sub> →	
				PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE		D <sub>f</sub> →	
<b>ORGANIC IMPURITIES</b>		<input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21		<b>UNCOMPACTED VOID CONTENT</b>			
ORGANIC PLATE NO. →				<input type="checkbox"/> ASTM C1252 <input type="checkbox"/>		% →	
<b>CARBONATES IN AGGREGATE</b>				<b>FLAT &amp; ELONGATED PARTICLES</b>			
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →				<input type="checkbox"/> ASTM D4791 <input type="checkbox"/>		BY WEIGHT, % →	
				DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5		BY NUMBER, % →	

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-13-12**

Job No. **3151JM098**

Event / Invoice No. **315200185-25**

Lab No. **0981118-**

Authorized By **C. SANCHEZ**

Date **10-22-12**

Sampled By **CLIENT**

Date **11-02-12**

Submitted By **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Aggregate **VARIABLE**  
Sample Source / Location **CHV-101S 12.5-14'**  
Special Instructions: **0981118-5**

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT**

Date **11-02-12**

### TEST RESULTS

SIEVE ANALYSIS <input checked="" type="checkbox"/> ASTM C136 <input type="checkbox"/> AASHTO T27			PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION				
4 IN. - 100.0			<b>UNIT WEIGHT &amp; VOIDS</b> FINE AGGREGATE UNIT WEIGHT, PCF →			
3 - 75.0			<input type="checkbox"/> ASTM C29 <input type="checkbox"/> AASHTO T19 VOIDS, % →			
2 - 50.0			<input type="checkbox"/> RODDING <input type="checkbox"/> JIGGING <input type="checkbox"/> LOOSE COARSE AGGREGATE UNIT WEIGHT, PCF →			
1 1/2 - 37.5			VOIDS, % →			
1 1/4 - 31.5						
1 - 25.0	<b>100</b>					
3/4 - 19.0	<b>94</b>					
1/2 - 12.5	<b>84</b>					
3/8 - 9.5	<b>78</b>					
1/4 - 6.3	<b>66</b>					
NO. 4 - 4.75	<b>60</b>					
8 - 2.36	<b>50</b>					
10 - 2.00	<b>47</b>					
16 - 1.18	<b>42</b>					
30 - .600	<b>35</b>					
40 - .425	<b>33</b>					
50 - .300	<b>29</b>					
100 - .150	<b>23</b>					
<b>FINER THAN NO. 200</b>						
<input checked="" type="checkbox"/> ASTM C117 <b>17.4</b>						
<input type="checkbox"/> AASHTO T11						
<b>FINENESS MODULUS, ASTM C125 →</b>						
<b>LIQUID &amp; PLASTIC PROPERTIES</b>						
<input type="checkbox"/> ASTM D4318 <input type="checkbox"/> AASHTO T89 & T90						
METHOD <input type="checkbox"/> A <input type="checkbox"/> B RESULT SPECIFICATION						
LIQUID LIMIT						
PLASTIC LIMIT						
PLASTICITY INDEX						
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO						
<b>CLEANNESS VALUE</b> CA227 →						
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21						
ORGANIC PLATE NO. →						
<b>CARBONATES IN AGGREGATE</b>						
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →						
			<b>UNIT WEIGHT &amp; VOIDS</b> FINE AGGREGATE UNIT WEIGHT, PCF →			
			<input type="checkbox"/> ASTM C29 <input type="checkbox"/> AASHTO T19 VOIDS, % →			
			<input type="checkbox"/> RODDING <input type="checkbox"/> JIGGING <input type="checkbox"/> LOOSE COARSE AGGREGATE UNIT WEIGHT, PCF →			
			VOIDS, % →			
			<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
			FINE AGGREGATE			
			<input type="checkbox"/> ASTM C128 <input type="checkbox"/> AASHTO T84			
			AGGREGATE DRIED			
			<input type="checkbox"/> YES <input type="checkbox"/> NO			
			BULK SPECIFIC GRAVITY →			
			BULK SPECIFIC GRAVITY (SSD) →			
			APPARENT SPECIFIC GRAVITY →			
			ABSORPTION, % →			
			COARSE AGGREGATE			
			<input type="checkbox"/> ASTM C127 <input type="checkbox"/> AASHTO T85			
			AGGREGATE DRIED			
			<input type="checkbox"/> YES <input type="checkbox"/> NO			
			BULK SPECIFIC GRAVITY →			
			BULK SPECIFIC GRAVITY (SSD) →			
			APPARENT SPECIFIC GRAVITY →			
			ABSORPTION, % →			
			<b>SAND EQUIVALENT VALUE</b> <input type="checkbox"/> ASTM D2419 <input type="checkbox"/> AASHTO T178 % →			
			<b>RESISTANCE TO DEGRADATION</b>			
			SMALL COARSE AGGREGATE			
			<input type="checkbox"/> ASTM C131 <input type="checkbox"/> AASHTO T96 GRADING			
			100 REV., % LOSS →			
			500 REV., % LOSS →			
			LARGE COARSE AGGREGATE			
			<input type="checkbox"/> ASTM C535 GRADING			
			200 REV., % LOSS →			
			1000 REV., % LOSS →			
			<b>LIGHTWEIGHT PIECES</b>			
			<input type="checkbox"/> ASTM C123 <input type="checkbox"/> AASHTO T113			
			FINE AGGREGATE, % →			
			COARSE AGGREGATE, % →			
			<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>			
			<input type="checkbox"/> ASTM C142 <input type="checkbox"/> AASHTO T112			
			FINE AGGREGATE, % →			
			COARSE AGGREGATE, % →			
			<b>FRACTURED FACES</b> COARSE AGGREGATE BY WEIGHT			
			<input type="checkbox"/> ASTM D5821 <input type="checkbox"/> FLH T507 <input type="checkbox"/> FAA <input type="checkbox"/>			
			ONE OR MORE FACES, % →			
			TWO OR MORE FACES, % →			
			<b>DURABILITY INDEX</b> <input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210			
			PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE			
			D <sub>c</sub> →			
			D <sub>f</sub> →			
			<b>UNCOMPACTED VOID CONTENT</b> <input type="checkbox"/> ASTM C1252 % →			
			<b>FLAT &amp; ELONGATED PARTICLES</b> <input type="checkbox"/> ASTM D4791 <input type="checkbox"/>			
			BY WEIGHT, % →			
			DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5 <input type="checkbox"/>			
			BY NUMBER, % →			

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY 





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Project **RICO INITIAL SOLIDS**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Aggregate **VARIABLE**  
Sample Source / Location **CHV-101S 7.5-9'**  
Special Instructions: **0981118-3**

Date of Report **12-13-12**  
Job No. **3151JM098**  
Event / Invoice No. **315200185-25** Lab No. **0981118-**  
Authorized By **C. SANCHEZ** Date **10-22-12**  
Sampled By **CLIENT** Date **11-02-12**  
Submitted By **J. GISSEMAN** Date **11-14-12**  
Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT** Date **11-02-12**

### TEST RESULTS

SIEVE ANALYSIS		<input checked="" type="checkbox"/> ASTM C136	<input type="checkbox"/> AASHTO T27	PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION					
4 IN. - 100.0				<b>UNIT WEIGHT &amp; VOIDS</b> FINE AGGREGATE UNIT WEIGHT, PCF →			
3 - 75.0				<input type="checkbox"/> ASTM C29 <input type="checkbox"/> AASHTO T19 VOIDS, % →			
2 - 50.0				<input type="checkbox"/> RODDING <input type="checkbox"/> JIGGING <input type="checkbox"/> LOOSE COARSE AGGREGATE UNIT WEIGHT, PCF →			
1 1/2 - 37.5				VOIDS, % →			
1 1/4 - 31.5							
1 - 25.0				<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
3/4 - 19.0				FINE AGGREGATE BULK SPECIFIC GRAVITY →			
1/2 - 12.5				<input type="checkbox"/> ASTM C128 <input type="checkbox"/> AASHTO T84 BULK SPECIFIC GRAVITY (SSD) →			
3/8 - 9.5				AGGREGATE DRIED APPARENT SPECIFIC GRAVITY →			
1/4 - 6.3				<input type="checkbox"/> YES <input type="checkbox"/> NO ABSORPTION, % →			
NO. 4 - 4.75							
8 - 2.36				COARSE AGGREGATE BULK SPECIFIC GRAVITY →			
10 - 2.00				<input type="checkbox"/> ASTM C127 <input type="checkbox"/> AASHTO T85 BULK SPECIFIC GRAVITY (SSD) →			
16 - 1.18				AGGREGATE DRIED APPARENT SPECIFIC GRAVITY →			
30 - .600				<input type="checkbox"/> YES <input type="checkbox"/> NO ABSORPTION, % →			
40 - .425							
50 - .300				<b>SAND EQUIVALENT VALUE</b> <input type="checkbox"/> ASTM D2419 <input type="checkbox"/> AASHTO T176 % →			
100 - .150							
<b>FINER THAN NO. 200</b>				<b>RESISTANCE TO DEGRADATION</b>			
<input checked="" type="checkbox"/> ASTM C117	<b>13.8</b>			SMALL COARSE AGGREGATE 100 REV., % LOSS →			
<input type="checkbox"/> AASHTO T11				<input type="checkbox"/> ASTM C131 <input type="checkbox"/> AASHTO T96 GRADING 500 REV., % LOSS →			
<b>FINENESS MODULUS, ASTM C125 →</b>				LARGE COARSE AGGREGATE 200 REV., % LOSS →			
				<input type="checkbox"/> ASTM C535 GRADING 1000 REV., % LOSS →			
<b>LIQUID &amp; PLASTIC PROPERTIES</b>				<b>LIGHTWEIGHT PIECES</b>			
<input type="checkbox"/> ASTM D4318 <input type="checkbox"/> AASHTO T89 & T90				<input type="checkbox"/> ASTM C123 <input type="checkbox"/> AASHTO T113			
METHOD <input type="checkbox"/> A <input type="checkbox"/> B RESULT SPECIFICATION							
LIQUID LIMIT				<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>			
PLASTIC LIMIT				<input type="checkbox"/> ASTM C142 <input type="checkbox"/> AASHTO T112			
PLASTICITY INDEX							
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO				<b>FRACTURED FACES</b> COARSE AGGREGATE BY WEIGHT			
				<input type="checkbox"/> ASTM D5821 <input type="checkbox"/> FLH T507 <input type="checkbox"/> FAA <input type="checkbox"/>			
				ONE OR MORE FACES, % →			
				TWO OR MORE FACES, % →			
<b>CLEANNES VALUE</b> CA227 →				<b>DURABILITY INDEX</b> <input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210			
				PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE		D <sub>c</sub> →	
						D <sub>f</sub> →	
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21				<b>UNCOMPACTED VOID CONTENT</b> <input type="checkbox"/> ASTM C1252 <input type="checkbox"/>		% →	
ORGANIC PLATE NO. →							
<b>CARBONATES IN AGGREGATE</b>				<b>FLAT &amp; ELONGATED PARTICLES</b> <input type="checkbox"/> ASTM D4791 <input type="checkbox"/>		BY WEIGHT, % →	
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →				DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5 <input type="checkbox"/>		BY NUMBER, % →	

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY:





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-13-12**

Job No. **3151JM098**

Event / Invoice No. **315200185-25**

Lab No. **0981118-**

Authorized By **C. SANCHEZ**

Date **10-22-12**

Sampled By **CLIENT**

Date **11-02-12**

Submitted By **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS**

Location **RICO, COLORADO**

Contractor **FLARE CONSTRUCTION**

Arch. / Engr. **ANDERSON ENGINEERING**

Type / Use of Aggregate **VARIABLE**

Supplier / Source **BORINGS**

Sample Source / Location **CHV-101S 27.5-29'**

Source / Location Desig. By **CLIENT**

Date **11-02-12**

Special Instructions: **0981118-10**

### TEST RESULTS

SIEVE ANALYSIS		ASTM C136	AASHTO T27	PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING						
4 IN. - 100.0				<b>UNIT WEIGHT &amp; VOIDS</b>			
3 - 75.0				FINE AGGREGATE		UNIT WEIGHT, PCF →	
2 - 50.0				VOIDS, % →			
1 1/2 - 37.5				COARSE AGGREGATE		UNIT WEIGHT, PCF →	
1 1/4 - 31.5				VOIDS, % →			
1 - 25.0				<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
3/4 - 19.0				FINE AGGREGATE		BULK SPECIFIC GRAVITY →	
1/2 - 12.5				BULK SPECIFIC GRAVITY (SSD) →			
3/8 - 9.5				APPARENT SPECIFIC GRAVITY →			
1/4 - 6.3				ABSORPTION, % →			
NO. 4 - 4.75				COARSE AGGREGATE		BULK SPECIFIC GRAVITY →	
8 - 2.36				BULK SPECIFIC GRAVITY (SSD) →			
10 - 2.00				APPARENT SPECIFIC GRAVITY →			
16 - 1.18				ABSORPTION, % →			
30 - .600				<b>SAND EQUIVALENT VALUE</b>			
40 - .425				ASTM D2419 AASHTO T176		% →	
50 - .300				<b>RESISTANCE TO DEGRADATION</b>			
100 - .150				SMALL COARSE AGGREGATE		100 REV., % LOSS →	
				ASTM C131 AASHTO T96 GRADING		500 REV., % LOSS →	
				LARGE COARSE AGGREGATE		200 REV., % LOSS →	
				ASTM C535 GRADING		1000 REV., % LOSS →	
<b>FINER THAN NO. 200</b>				<b>LIGHTWEIGHT PIECES</b>			
<input checked="" type="checkbox"/> ASTM C117	<b>14.0</b>			ASTM C123 AASHTO T113		FINE AGGREGATE, % →	
<input type="checkbox"/> AASHTO T11						COARSE AGGREGATE, % →	
<b>FINENESS MODULUS, ASTM C125 →</b>				<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>			
<b>LIQUID &amp; PLASTIC PROPERTIES</b>				ASTM C142 AASHTO T112		FINE AGGREGATE, % →	
ASTM D4318 AASHTO T89 & T90						COARSE AGGREGATE, % →	
METHOD <input type="checkbox"/> A <input type="checkbox"/> B RESULT SPECIFICATION				<b>FRACTURED FACES</b>			
LIQUID LIMIT				COARSE AGGREGATE BY WEIGHT		ONE OR MORE FACES, % →	
PLASTIC LIMIT				ASTM D5821 FLH T507 FAA		TWO OR MORE FACES, % →	
PLASTICITY INDEX							
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO				<b>DURABILITY INDEX</b>			
				ASTM D3744 AASHTO T210		D <sub>c</sub> →	
<b>CLEANNESS VALUE</b> CA227 →				PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE		D <sub>f</sub> →	
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21				<b>UNCOMPACTED VOID CONTENT</b>			
ORGANIC PLATE NO. →				ASTM C1252		% →	
<b>CARBONATES IN AGGREGATE</b>				<b>FLAT &amp; ELONGATED PARTICLES</b>			
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →				ASTM D4791		BY WEIGHT, % →	
				DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5		BY NUMBER, % →	

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Date of Report 12-13-12

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Job No. **3151JM098**

Event / Invoice No. **315200185-25**

Lab No. **0981118-**

Authorized By **C. SANCHEZ**

Date **10-22-12**

Sampled By **CLIENT**

Date **11-02-12**

Submitted By **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Aggregate **VARIABLE**  
Sample Source / Location **CHV-101S 45-46.5'**  
Special Instructions: **0981118-12**

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT**

Date **11-02-12**

### TEST RESULTS

SIEVE ANALYSIS <input checked="" type="checkbox"/> ASTM C136 <input type="checkbox"/> AASHTO T27			PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION				
4 IN. - 100.0			<b>UNIT WEIGHT &amp; VOIDS</b> FINE AGGREGATE UNIT WEIGHT, PCF →			
3 - 75.0			<input type="checkbox"/> ASTM C29 <input type="checkbox"/> AASHTO T19 VOIDS, % →			
2 - 50.0			<input type="checkbox"/> RODDING <input type="checkbox"/> JIGGING <input type="checkbox"/> LOOSE COARSE AGGREGATE UNIT WEIGHT, PCF →			
1 1/2 - 37.5			VOIDS, % →			
1 1/4 - 31.5						
1 - 25.0			<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
3/4 - 19.0			FINE AGGREGATE BULK SPECIFIC GRAVITY →			
1/2 - 12.5			<input type="checkbox"/> ASTM C128 <input type="checkbox"/> AASHTO T84 BULK SPECIFIC GRAVITY (SSD) →			
3/8 - 9.5			AGGREGATE DRIED APPARENT SPECIFIC GRAVITY →			
1/4 - 6.3			<input type="checkbox"/> YES <input type="checkbox"/> NO ABSORPTION, % →			
NO. 4 - 4.75			COARSE AGGREGATE BULK SPECIFIC GRAVITY →			
8 - 2.36			<input type="checkbox"/> ASTM C127 <input type="checkbox"/> AASHTO T85 BULK SPECIFIC GRAVITY (SSD) →			
10 - 2.00			AGGREGATE DRIED APPARENT SPECIFIC GRAVITY →			
16 - 1.18			<input type="checkbox"/> YES <input type="checkbox"/> NO ABSORPTION, % →			
30 - .600						
40 - .425			<b>SAND EQUIVALENT VALUE</b> <input type="checkbox"/> ASTM D2419 <input type="checkbox"/> AASHTO T176 % →			
50 - .300						
100 - .150						
<b>FINER THAN NO. 200</b>			<b>RESISTANCE TO DEGRADATION</b>			
<input checked="" type="checkbox"/> ASTM C117	<b>15.3</b>		SMALL COARSE AGGREGATE 100 REV., % LOSS →			
<input type="checkbox"/> AASHTO T11			<input type="checkbox"/> ASTM C131 <input type="checkbox"/> AASHTO T96 GRADING 500 REV., % LOSS →			
			LARGE COARSE AGGREGATE 200 REV., % LOSS →			
			<input type="checkbox"/> ASTM C535 GRADING 1000 REV., % LOSS →			
<b>FINENESS MODULUS, ASTM C125 →</b>						
<b>LIQUID &amp; PLASTIC PROPERTIES</b>			<b>LIGHTWEIGHT PIECES</b>			
<input type="checkbox"/> ASTM D4318 <input type="checkbox"/> AASHTO T89 & T90			<input type="checkbox"/> ASTM C123 <input type="checkbox"/> AASHTO T113			
METHOD <input type="checkbox"/> A <input type="checkbox"/> B RESULT SPECIFICATION			FINE AGGREGATE, % →			
LIQUID LIMIT			COARSE AGGREGATE, % →			
PLASTIC LIMIT						
PLASTICITY INDEX			<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>			
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO			<input type="checkbox"/> ASTM C142 <input type="checkbox"/> AASHTO T112			
			FINE AGGREGATE, % →			
			COARSE AGGREGATE, % →			
<b>CLEANNES VALUE</b> CA227 →			<b>FRACTURED FACES</b> COARSE AGGREGATE BY WEIGHT			
			<input type="checkbox"/> ASTM D5821 <input type="checkbox"/> FLH T507 <input type="checkbox"/> FAA <input type="checkbox"/>			
			ONE OR MORE FACES, % →			
			TWO OR MORE FACES, % →			
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21			<b>DURABILITY INDEX</b> <input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210			
ORGANIC PLATE NO. →			PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE		D <sub>c</sub> →	
					D <sub>f</sub> →	
			<b>UNCOMPACTED VOID CONTENT</b> <input type="checkbox"/> ASTM C1252 <input type="checkbox"/>		% →	
<b>CARBONATES IN AGGREGATE</b>			<b>FLAT &amp; ELONGATED PARTICLES</b> <input type="checkbox"/> ASTM D4791 <input type="checkbox"/>		BY WEIGHT, % →	
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →			DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5 <input type="checkbox"/>		BY NUMBER, % →	

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **01-08-13**  
Job No. **3151JM098**  
Event / Invoice No. **31520185-20** Lab No. **0981113-2**  
Authorized by **CHRIS SANCHEZ** Date **10-22-12**  
Sampled by **CLIENT** Date **11-11-12**  
Submitted by **J. GISSEMAN** Date **11-14-12**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **1" MINUS CLAYEY SAND WITH GRAVEL**  
Sample Source / Location **MW-202 SONIC, 1.5-12'**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT** Date **11-11-12**

### TEST RESULTS

SIEVE ANALYSIS : ASTM C136 FINER THAN NO. 200 : ASTM C117			LABORATORY COMPACTION CHARACTERISTICS : AASHTO T99 METHOD C		
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION			
6					
5					
4					
3					
2					
1 1/2					
1	100				
3/4	97				
1/2	89				
3/8	79				
1/4	69				
No. 4	65				
8	54				
10	53				
16	46				
30	41				
40	38				
50	35				
100	29				
200	25				

TEST PROCEDURE		RESULT	SPECS	TEST PROCEDURE		RESULT	SPECS
<b>LIQUID &amp; PLASTIC PROPERTIES : AASHTO T89, 90</b> METHOD B      LIQUID LIMIT → <b>30</b> ESTIMATED % RETAINED ON NO. 40 <b>62</b> PLASTIC LIMIT → <b>21</b> SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO      PLASTICITY INDEX → <b>9</b>				<b>RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :</b> GRADING 100 REV. % LOSS → GRADING 500 REV. % LOSS →			
<b>MOISTURE CONTENT : AASHTO T265</b> PORTION TESTED <b>FULL</b> % DRY WEIGHT → <b>20.9</b>				<b>SPECIFIC GRAVITY :</b> MAX. PARTICLE SIZE, IN.      SPECIFIC GRAVITY @ 20°C →			
<b>EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :</b> <input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % → MAXIMUM SWELL PRESSURE, KSF → SURCHARGE, KSF INITIAL WATER CONTENT, %      DRY DENSITY, PCF				<b>pH DETERMINATION :</b> pH → <b>SOLUBLE SALTS :</b> PPM → <b>MINIMUM RESISTIVITY :</b> OHM-CM →			
<b>SOIL CLASSIFICATION : ASTM D2487</b>				GROUP SYMBOL: <b>SC</b> NAME: <b>CLAYEY SAND WITH GRAVEL</b>			

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**

The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## LABORATORY REPORT

Client **ANDERSON ENGINEERING COMPANY, INC.**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Project **RICO INITIAL SOLIDS REMOVAL & DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **VARIOUS**  
Sample Source / Location **MW-202 SONIC**  
Reference: **ASTM**  
Special Instructions:

Date of Report **12-11-12**  
Job No. **3151JM098**  
Event / Invoice No. **31520185-20** Lab No.  
Authorized By **C. SANCHEZ** Date **10-22-12**  
Sampled By **CLIENT** Date **11-11-12**  
Submitted By **J. GISSEMAN** Date **11-14-12**  
Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **11-14-12** Date

### TEST RESULTS

<u>ELEVATION (FT)</u>	<u>MOISTURE CONTENT (%)</u>	<u>ATTERBERGS:</u>	<u>LL</u>	<u>PL</u>	<u>PI</u>	<u>ORGANIC CONTENT (%)</u>
0-1.5'	19.0					
1.5-6'	20.0					
6-9'	14.1					
9-12'	18.2					
12-18'	24.0					
18-23'	13.1					
23-30'	36.0					
30-35.5'	9.7					

Comments: **SEE ADDITIONAL PHYSICAL PROPERTIES REPORTS FOR GRADATIONS**

Copies To: **CLIENT (2)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western Technologies Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-11-12**

Job No. **3151JM098**

Event / Invoice No. **315200185-20**

Lab No. **0981113**

Authorized By **C. SANCHEZ**

Date **10-24-12**

Sampled By **CLIENT**

Date **11-11-12**

Submitted By **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS**

Location **RICO, COLORADO**

Contractor **FLARE CONSTRUCTION**

Arch. / Engr. **ANDERSON ENGINEERING**

Type / Use of Aggregate **VARIABLE**

Supplier / Source **BORINGS**

Sample Source / Location **MW-202 SONIC 0-1.5'**

Source / Location Desig. By **CLIENT**

Date **11-11-12**

Special Instructions: **0981113-1**

### TEST RESULTS

SIEVE ANALYSIS		<input checked="" type="checkbox"/> ASTM C136	<input type="checkbox"/> AASHTO T27	PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION					
4 IN. - 100.0				<b>UNIT WEIGHT &amp; VOIDS</b>			
3 - 75.0				FINE AGGREGATE		UNIT WEIGHT, PCF →	
2 - 50.0				<input type="checkbox"/> ASTM C29 <input type="checkbox"/> AASHTO T19		VOIDS, % →	
1 1/2 - 37.5				<input type="checkbox"/> RODDING <input type="checkbox"/> JIGGING <input type="checkbox"/> LOOSE		UNIT WEIGHT, PCF →	
1 1/4 - 31.5				COARSE AGGREGATE		VOIDS, % →	
1 - 25.0	<b>100</b>			<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
3/4 - 19.0	<b>63</b>			FINE AGGREGATE		BULK SPECIFIC GRAVITY →	
1/2 - 12.5	<b>55</b>			<input type="checkbox"/> ASTM C128 <input type="checkbox"/> AASHTO T84		BULK SPECIFIC GRAVITY (SSD) →	
3/8 - 9.5	<b>51</b>			AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
1/4 - 6.3	<b>45</b>			<input type="checkbox"/> YES <input type="checkbox"/> NO		ABSORPTION, % →	
NO. 4 - 4.75	<b>43</b>			COARSE AGGREGATE		BULK SPECIFIC GRAVITY →	
8 - 2.36	<b>38</b>			<input type="checkbox"/> ASTM C127 <input type="checkbox"/> AASHTO T85		BULK SPECIFIC GRAVITY (SSD) →	
10 - 2.00	<b>37</b>			AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
16 - 1.18	<b>33</b>			<input type="checkbox"/> YES <input type="checkbox"/> NO		ABSORPTION, % →	
30 - .600	<b>30</b>			<b>SAND EQUIVALENT VALUE</b>			
40 - .425	<b>28</b>			<input type="checkbox"/> ASTM D2419 <input type="checkbox"/> AASHTO T176		% →	
50 - .300	<b>26</b>			<b>RESISTANCE TO DEGRADATION</b>			
100 - .150	<b>20</b>			SMALL COARSE AGGREGATE		100 REV., % LOSS →	
				<input type="checkbox"/> ASTM C131 <input type="checkbox"/> AASHTO T96		GRADING 500 REV., % LOSS →	
				LARGE COARSE AGGREGATE		200 REV., % LOSS →	
				<input type="checkbox"/> ASTM C535		GRADING 1000 REV., % LOSS →	
<b>FINER THAN NO. 200</b>							
<input checked="" type="checkbox"/> ASTM C117		<b>13.0</b>					
<input type="checkbox"/> AASHTO T11							
<b>FINENESS MODULUS, ASTM C125 →</b>							
<b>LIQUID &amp; PLASTIC PROPERTIES</b>				<b>LIGHTWEIGHT PIECES</b>			
<input type="checkbox"/> ASTM D4318 <input checked="" type="checkbox"/> AASHTO T89 & T90				<input type="checkbox"/> ASTM C123 <input type="checkbox"/> AASHTO T113		FINE AGGREGATE, % →	
METHOD <input type="checkbox"/> A <input checked="" type="checkbox"/> B		RESULT				COARSE AGGREGATE, % →	
LIQUID LIMIT		<b>NV</b>					
PLASTIC LIMIT		<b>NV</b>					
PLASTICITY INDEX		<b>NP</b>					
SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO				<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>		FINE AGGREGATE, % →	
				<input type="checkbox"/> ASTM C142 <input type="checkbox"/> AASHTO T112		COARSE AGGREGATE, % →	
<b>CLEANNESS VALUE</b> CA227 →				<b>FRACTURED FACES</b>			
				COARSE AGGREGATE BY WEIGHT		ONE OR MORE FACES, % →	
				<input type="checkbox"/> ASTM D5821 <input type="checkbox"/> FLH T507 <input type="checkbox"/> FAA <input type="checkbox"/>		TWO OR MORE FACES, % →	
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21				<b>DURABILITY INDEX</b>			
ORGANIC PLATE NO. →				<input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210		D <sub>c</sub> →	
				PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE		D <sub>f</sub> →	
<b>CARBONATES IN AGGREGATE</b>				<b>UNCOMPACTED VOID CONTENT</b>			
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →				<input type="checkbox"/> ASTM C1252 <input type="checkbox"/>		% →	
				<b>FLAT &amp; ELONGATED PARTICLES</b>			
				<input type="checkbox"/> ASTM D4791 <input type="checkbox"/>		BY WEIGHT, % →	
				DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5 <input type="checkbox"/>		BY NUMBER, % →	

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-14-12**

Job No. **3151JM098**

Event / Invoice No. **31520185-20**

Lab No. **0981113-2**

Authorized by **CHRIS SANCHEZ**

Date **10-22-12**

Sampled by **CLIENT**

Date **11-11-12**

Submitted by **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **1" MINUS CLAYEY SAND WITH GRAVEL**  
Sample Source / Location **MW-202 SONIC, 1.5-6'**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT**

Date **11-11-12**

### TEST RESULTS

SIEVE ANALYSIS : ASTM C136 FINER THAN NO. 200 : ASTM C117			LABORATORY COMPACTION CHARACTERISTICS : AASHTO T99 METHOD C		
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION			
6					
5					
4					
3					
2					
1 1/2					
1	100				
3/4	97				
1/2	89				
3/8	79				
1/4	69				
No. 4	65				
8	54				
10	53				
16	46				
30	41				
40	38				
50	35				
100	29				
200	25				

TEST PROCEDURE	RESULT	SPECS	TEST PROCEDURE	RESULT	SPECS
<b>LIQUID &amp; PLASTIC PROPERTIES : AASHTO T89, 90</b> METHOD B LIQUID LIMIT → <b>30</b> ESTIMATED % RETAINED ON NO. 40 <b>62</b> PLASTIC LIMIT → <b>21</b> SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO PLASTICITY INDEX → <b>9</b>			<b>RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :</b> GRADING 100 REV, % LOSS → GRADING 500 REV, % LOSS →		
<b>MOISTURE CONTENT : AASHTO T265</b> PORTION TESTED <b>FULL</b> % DRY WEIGHT → <b>20.9</b>			<b>SPECIFIC GRAVITY :</b> MAX. PARTICLE SIZE, IN. SPECIFIC GRAVITY @ 20°C →		
<b>EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :</b> <input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % MAXIMUM SWELL PRESSURE, KSF → SURCHARGE, KSF INITIAL WATER CONTENT, % DRY DENSITY, PCF			<b>pH DETERMINATION :</b> pH → <b>SOLUBLE SALTS :</b> PPM → <b>MINIMUM RESISTIVITY :</b> OHM-CM →		
<b>SOIL CLASSIFICATION : ASTM D2487</b>			<b>GROUP SYMBOL: SC</b> <b>NAME: CLAYEY SAND WITH GRAVEL</b>		

SAMPLE PREPARATION: ☒ WET ☐ DRY  
RAMMER USED: ☒ 2 IN. CIRCULAR FACE ☐ OTHER  
☐ MECHANICAL ☒ MANUAL

PROJECT PROCTOR ID: **1111**  
MAXIMUM DENSITY, LBF/FT<sup>3</sup> → **128**  
OPTIMUM MOISTURE CONTENT, % → **9**

OVERSIZE AGGREGATE :  
ASSUMED BULK SPECIFIC GRAVITY : **2.65**  
ASSUMED ABSORPTION, % : **1.0**  
% OVERSIZE IN LAB SAMPLE : **0**

ASSUMED SPECIFIC GRAVITY  
IN ZERO AIR VOID CURVE : **2.65**

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-14-12**

Job No. **3151JM098**

Event / Invoice No. **31520185-20**

Lab No. **0981113-5**

Authorized by **CHRIS SANCHEZ**

Date **10-22-12**

Sampled by **CLIENT**

Date **11-11-12**

Submitted by **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **3/4" MINUS GRAVEL WITH SAND/CLAY**  
Sample Source / Location **MW-202 SONIC, 12-30'**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT**

Date **11-11-12**

### TEST RESULTS

SIEVE ANALYSIS : ASTM C136 FINER THAN NO. 200 : ASTM C117			LABORATORY COMPACTION CHARACTERISTICS : ASTM D698 METHOD C		
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION			
6					
5					
4					
3					
2					
1 1/2					
1					
3/4	100				
1/2	95				
3/8	91				
1/4	84				
No. 4	80				
8	65				
10	62				
16	49				
30	37				
40	32				
50	26				
100	16				
200	9.3				

TEST PROCEDURE		RESULT	SPECS	TEST PROCEDURE		RESULT	SPECS
<b>LIQUID &amp; PLASTIC PROPERTIES : AASHTO T89, 90</b> METHOD B LIQUID LIMIT → <b>30</b> ESTIMATED % RETAINED ON NO. 40 <b>68</b> PLASTIC LIMIT → <b>21</b> SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO PLASTICITY INDEX → <b>9</b>				<b>RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :</b> GRADING 100 REV, % LOSS → GRADING 500 REV, % LOSS →			
<b>MOISTURE CONTENT : AASHTO T265</b> PORTION TESTED <b>FULL</b> % DRY WEIGHT → <b>24.0</b>				<b>SPECIFIC GRAVITY :</b> MAX. PARTICLE SIZE, IN. SPECIFIC GRAVITY @ 20°C →			
<b>EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :</b> <input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % → MAXIMUM SWELL PRESSURE, KSF →				<b>pH DETERMINATION :</b> pH →			
SURCHARGE, KSF INITIAL WATER CONTENT, % DRY DENSITY, PCF				<b>SOLUBLE SALTS :</b> PPM →			
				<b>MINIMUM RESISTIVITY :</b> OHM-CM →			
<b>SOIL CLASSIFICATION : ASTM D2487</b>				<b>GROUP SYMBOL: SP-SC</b> <b>NAME: POORLY GRADED SAND WITH CLAY AND GRAVEL</b>			

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## LABORATORY REPORT

Client **ANDERSON ENGINEERING COMPANY, INC.**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Project **RICO INITIAL SOLIDS REMOVAL & DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **VARIOUS**  
Sample Source / Location **MW-204 SONIC**  
Reference: **ASTM**  
Special Instructions:

Date of Report **12-13-12**  
Job No. **3151JM098**  
Event / Invoice No. **31520185-26** Lab No.  
Authorized By **C. SANCHEZ** Date **10-22-12**  
Sampled By **CLIENT** Date **11-07-12**  
Submitted By **J. GISSEMAN** Date **11-14-12**  
Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT** Date **11-07-12**

### TEST RESULTS

<u>ELEVATION (FT)</u>	<u>MOISTURE CONTENT (%)</u>	<u>ATTERBERGS:</u>	<u>LL</u>	<u>PL</u>	<u>PI</u>	<u>ORGANIC CONTENT (%)</u>
0-7'	7.9					
7-10.5'	9.7		29	19	10	
10.5-12'	9.4					
12-15'	14.4		29	19	10	
21-25.5'	16.6					

Comments: **SEE ADDITIONAL PHYSICAL PROPERTIES REPORTS FOR  
GRADATIONS**

Copies To: **CLIENT (2)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-13-12**

Job No. **3151JM098**

Event / Invoice No. **315200185-26**

Lab No. **09811120**

Authorized By **C. SANCHEZ**

Date **10-22-12**

Sampled By **CLIENT**

Date **11-07-12**

Submitted By **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS**

Location **RICO, COLORADO**

Contractor **FLARE CONSTRUCTION**

Arch. / Engr. **ANDERSON ENGINEERING**

Type / Use of Aggregate **VARIABLE**

Supplier / Source **BORINGS**

Sample Source / Location **MW-204 SONIC 0-7'**

Source / Location Desig. By **CLIENT**

Date **11-07-12**

Special Instructions: **0981120-1**

### TEST RESULTS

SIEVE ANALYSIS			PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION				
4 IN. - 100.0			<b>UNIT WEIGHT &amp; VOIDS</b>			
3 - 75.0			FINE AGGREGATE UNIT WEIGHT, PCF →			
2 - 50.0			VOIDS, % →			
1 1/2 - 37.5			COARSE AGGREGATE UNIT WEIGHT, PCF →			
1 1/4 - 31.5			VOIDS, % →			
1 - 25.0	<b>100</b>					
3/4 - 19.0	<b>72</b>					
1/2 - 12.5	<b>56</b>					
3/8 - 9.5	<b>44</b>					
1/4 - 6.3	<b>32</b>					
NO. 4 - 4.75	<b>26</b>					
8 - 2.36	<b>18</b>					
10 - 2.00	<b>16</b>					
16 - 1.18	<b>13</b>					
30 - .600	<b>10</b>					
40 - .425	<b>8.6</b>					
50 - .300	<b>7.2</b>					
100 - .150	<b>4.9</b>					
<b>FINER THAN NO. 200</b>						
<input checked="" type="checkbox"/> ASTM C117						
3.0						
<input type="checkbox"/> AASHTO T11						
<b>FINENESS MODULUS, ASTM C125 →</b>						
<b>LIQUID &amp; PLASTIC PROPERTIES</b>						
<input type="checkbox"/> ASTM D4318 <input type="checkbox"/> AASHTO T89 & T90						
METHOD <input type="checkbox"/> A <input type="checkbox"/> B RESULT SPECIFICATION						
LIQUID LIMIT						
PLASTIC LIMIT						
PLASTICITY INDEX						
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO						
<b>CLEANNESS VALUE</b> CA227 →						
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21						
ORGANIC PLATE NO. →						
<b>CARBONATES IN AGGREGATE</b>						
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →						
			<b>DURABILITY INDEX</b> <input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210			
			PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE		D <sub>c</sub> →	
					D <sub>f</sub> →	
			<b>UNCOMPACTED VOID CONTENT</b> <input type="checkbox"/> ASTM C1252 <input type="checkbox"/>		% →	
			<b>FLAT &amp; ELONGATED PARTICLES</b> <input type="checkbox"/> ASTM D4791 <input type="checkbox"/>		BY WEIGHT, % →	
			DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5 <input type="checkbox"/>		BY NUMBER, % →	

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY

*[Signature]*





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-13-12**

Job No. **3151JM098**

Event / Invoice No. **315200185-26**

Lab No. **09811120**

Authorized By **C. SANCHEZ**

Date **10-22-12**

Sampled By **CLIENT**

Date **11-07-12**

Submitted By **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Aggregate **VARIABLE**

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**

Sample Source / Location **MW-204 SONIC 10.5-12'**

Supplier / Source **BORINGS**

Source / Location Desig. By **CLIENT**

Date **11-07-12**

Special Instructions: **0981120-3**

### TEST RESULTS

SIEVE ANALYSIS <input checked="" type="checkbox"/> ASTM C136 <input type="checkbox"/> AASHTO T27			PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION				
4 IN. - 100.0			<b>UNIT WEIGHT &amp; VOIDS</b>			
3 - 75.0			FINE AGGREGATE UNIT WEIGHT, PCF →			
2 - 50.0			VOIDS, % →			
1 1/2 - 37.5			COARSE AGGREGATE UNIT WEIGHT, PCF →			
1 1/4 - 31.5			VOIDS, % →			
1 - 25.0	<b>100</b>					
3/4 - 19.0	<b>87</b>					
1/2 - 12.5	<b>68</b>					
3/8 - 9.5	<b>54</b>					
1/4 - 6.3	<b>41</b>					
NO. 4 - 4.75	<b>33</b>					
8 - 2.36	<b>22</b>					
10 - 2.00	<b>19</b>					
16 - 1.18	<b>15</b>					
30 - .600	<b>11</b>					
40 - .425	<b>8.9</b>					
50 - .300	<b>7.4</b>					
100 - .150	<b>4.8</b>					
<b>FINER THAN NO. 200</b>						
<input checked="" type="checkbox"/> ASTM C117						
<input type="checkbox"/> AASHTO T11						
<b>2.6</b>						
<b>FINENESS MODULUS, ASTM C125 →</b>						
<b>LIQUID &amp; PLASTIC PROPERTIES</b>						
<input type="checkbox"/> ASTM D4318 <input type="checkbox"/> AASHTO T89 & T90						
METHOD <input type="checkbox"/> A <input type="checkbox"/> B RESULT SPECIFICATION						
LIQUID LIMIT						
PLASTIC LIMIT						
PLASTICITY INDEX						
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO						
<b>CLEANNES VALUE</b> CA227 →						
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21						
ORGANIC PLATE NO. →						
<b>CARBONATES IN AGGREGATE</b>						
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →						
			<b>UNIT WEIGHT &amp; VOIDS</b>			
			FINE AGGREGATE UNIT WEIGHT, PCF →			
			VOIDS, % →			
			COARSE AGGREGATE UNIT WEIGHT, PCF →			
			VOIDS, % →			
			<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
			FINE AGGREGATE			
			<input type="checkbox"/> ASTM C128 <input type="checkbox"/> AASHTO T84			
			BULK SPECIFIC GRAVITY →			
			BULK SPECIFIC GRAVITY (SSD) →			
			APPARENT SPECIFIC GRAVITY →			
			ABSORPTION, % →			
			COARSE AGGREGATE			
			<input type="checkbox"/> ASTM C127 <input type="checkbox"/> AASHTO T85			
			BULK SPECIFIC GRAVITY →			
			BULK SPECIFIC GRAVITY (SSD) →			
			APPARENT SPECIFIC GRAVITY →			
			ABSORPTION, % →			
			<b>SAND EQUIVALENT VALUE</b> <input type="checkbox"/> ASTM D2419 <input type="checkbox"/> AASHTO T176 % →			
			<b>RESISTANCE TO DEGRADATION</b>			
			SMALL COARSE AGGREGATE			
			<input type="checkbox"/> ASTM C131 <input type="checkbox"/> AASHTO T96 GRADING			
			100 REV., % LOSS →			
			500 REV., % LOSS →			
			LARGE COARSE AGGREGATE			
			<input type="checkbox"/> ASTM C535 GRADING			
			200 REV., % LOSS →			
			1000 REV., % LOSS →			
			<b>LIGHTWEIGHT PIECES</b>			
			<input type="checkbox"/> ASTM C123 <input type="checkbox"/> AASHTO T113			
			FINE AGGREGATE, % →			
			COARSE AGGREGATE, % →			
			<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>			
			<input type="checkbox"/> ASTM C142 <input type="checkbox"/> AASHTO T112			
			FINE AGGREGATE, % →			
			COARSE AGGREGATE, % →			
			<b>FRACTURED FACES</b> COARSE AGGREGATE BY WEIGHT			
			<input type="checkbox"/> ASTM D5821 <input type="checkbox"/> FLH T507 <input type="checkbox"/> FAA <input type="checkbox"/>			
			ONE OR MORE FACES, % →			
			TWO OR MORE FACES, % →			
			<b>DURABILITY INDEX</b> <input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210			
			PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE			
			D <sub>c</sub> →			
			D <sub>f</sub> →			
			<b>UNCOMPACTED VOID CONTENT</b> <input type="checkbox"/> ASTM C1252 % →			
			<b>FLAT &amp; ELONGATED PARTICLES</b> <input type="checkbox"/> ASTM D4791 <input type="checkbox"/>			
			BY WEIGHT, % →			
			DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5			
			BY NUMBER, % →			

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-13-12**

Job No. **3151JM098**

Event / Invoice No. **315200185-26**

Lab No. **09811120**

Authorized By **C. SANCHEZ**

Date **10-22-12**

Sampled By **CLIENT**

Date **11-07-12**

Submitted By **J. GISSEMAN**

Date **11-14-12**

Project **RICO INITIAL SOLIDS**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Aggregate **VARIABLE**

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**

Sample Source / Location **MW-204 SONIC 21-25.5'**

Supplier / Source **BORINGS**

Source / Location Desig. By **CLIENT**

Date **11-07-12**

Special Instructions: **0981120-5**

### TEST RESULTS

SIEVE ANALYSIS		<input checked="" type="checkbox"/> ASTM C136	<input type="checkbox"/> AASHTO T27	PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION					
4 IN. - 100.0				<b>UNIT WEIGHT &amp; VOIDS</b>			
3 - 75.0				FINE AGGREGATE		UNIT WEIGHT, PCF →	
2 - 50.0				<input type="checkbox"/> ASTM C29 <input type="checkbox"/> AASHTO T19		VOIDS, % →	
1 1/2 - 37.5				<input type="checkbox"/> RODDING <input type="checkbox"/> JIGGING <input type="checkbox"/> LOOSE		UNIT WEIGHT, PCF →	
1 1/4 - 31.5				COARSE AGGREGATE		VOIDS, % →	
1 - 25.0	<b>100</b>			<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
3/4 - 19.0	<b>69</b>			FINE AGGREGATE		BULK SPECIFIC GRAVITY →	
1/2 - 12.5	<b>59</b>			<input type="checkbox"/> ASTM C128 <input type="checkbox"/> AASHTO T84		BULK SPECIFIC GRAVITY (SSD) →	
3/8 - 9.5	<b>56</b>			AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
1/4 - 6.3	<b>49</b>			<input type="checkbox"/> YES <input type="checkbox"/> NO		ABSORPTION, % →	
NO. 4 - 4.75	<b>46</b>			COARSE AGGREGATE		BULK SPECIFIC GRAVITY →	
8 - 2.36	<b>37</b>			<input type="checkbox"/> ASTM C127 <input type="checkbox"/> AASHTO T85		BULK SPECIFIC GRAVITY (SSD) →	
10 - 2.00	<b>35</b>			AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
16 - 1.18	<b>29</b>			<input type="checkbox"/> YES <input type="checkbox"/> NO		ABSORPTION, % →	
30 - .600	<b>24</b>			<b>SAND EQUIVALENT VALUE</b>			
40 - .425	<b>22</b>			<input type="checkbox"/> ASTM D2419 <input type="checkbox"/> AASHTO T176		% →	
50 - .300	<b>18</b>			<b>RESISTANCE TO DEGRADATION</b>			
100 - .150	<b>12</b>			SMALL COARSE AGGREGATE		100 REV., % LOSS →	
<b>FINER THAN NO. 200</b>				<input type="checkbox"/> ASTM C131 <input type="checkbox"/> AASHTO T96		GRADING 500 REV., % LOSS →	
<input checked="" type="checkbox"/> ASTM C117	<b>7.6</b>			LARGE COARSE AGGREGATE		200 REV., % LOSS →	
<input type="checkbox"/> AASHTO T11				<input type="checkbox"/> ASTM C535		GRADING 1000 REV., % LOSS →	
<b>FINENESS MODULUS, ASTM C125 →</b>				<b>LIGHTWEIGHT PIECES</b>			
				<input type="checkbox"/> ASTM C123 <input type="checkbox"/> AASHTO T113		FINE AGGREGATE, % →	
						COARSE AGGREGATE, % →	
<b>LIQUID &amp; PLASTIC PROPERTIES</b>				<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>			
<input type="checkbox"/> ASTM D4318 <input type="checkbox"/> AASHTO T89 & T90				<input type="checkbox"/> ASTM C142 <input type="checkbox"/> AASHTO T112		FINE AGGREGATE, % →	
METHOD <input type="checkbox"/> A <input type="checkbox"/> B RESULT SPECIFICATION						COARSE AGGREGATE, % →	
LIQUID LIMIT							
PLASTIC LIMIT							
PLASTICITY INDEX							
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO				<b>FRACTURED FACES</b>			
				COARSE AGGREGATE BY WEIGHT		ONE OR MORE FACES, % →	
				<input type="checkbox"/> ASTM D5821 <input type="checkbox"/> FLH T507 <input type="checkbox"/> FAA <input type="checkbox"/>		TWO OR MORE FACES, % →	
<b>CLEANNES VALUE</b> CA227 →				<b>DURABILITY INDEX</b>			
				<input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210		D <sub>c</sub> →	
				PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE		D <sub>f</sub> →	
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21				<b>UNCOMPACTED VOID CONTENT</b>			
ORGANIC PLATE NO. →				<input type="checkbox"/> ASTM C1252 <input type="checkbox"/>		% →	
<b>CARBONATES IN AGGREGATE</b>				<b>FLAT &amp; ELONGATED PARTICLES</b>			
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →				<input type="checkbox"/> ASTM D4791 <input type="checkbox"/>		BY WEIGHT, % →	
				DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5 <input type="checkbox"/>		BY NUMBER, % →	

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-14-12**

Job No. **3151JM098**

Event / Invoice No. **31520185-26**

Authorized by **CHRIS SANCHEZ**

Sampled by **CLIENT**

Submitted by **J. GISSEMAN**

Lab No. **0981120-1**

Date **10-22-12**

Date **11-07-12**

Date **11-14-12**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **VARIABLE**  
Sample Source / Location **MW-204, 0-25.5'**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT**

Date **11-14-12**

### TEST RESULTS

SIEVE ANALYSIS : FINER THAN NO. 200 :			LABORATORY COMPACTION CHARACTERISTICS : ASTM D698 METHOD C				
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION					
			SAMPLE PREPARATION: <input checked="" type="checkbox"/> WET <input type="checkbox"/> DRY RAMMER USED: <input checked="" type="checkbox"/> 2 IN. CIRCULAR FACE <input type="checkbox"/> OTHER <input type="checkbox"/> MECHANICAL <input checked="" type="checkbox"/> MANUAL PROJECT PROCTOR ID: <b>63</b> MAXIMUM DENSITY, LB/FT <sup>3</sup> → <b>125.9</b> OPTIMUM MOISTURE CONTENT, % → <b>9.9</b> OVERSIZE AGGREGATE : ASSUMED BULK SPECIFIC GRAVITY : <b>2.65</b> ASSUMED ABSORPTION, % : <b>1.0</b> % OVERSIZE IN LAB SAMPLE : <b>20</b> ASSUMED SPECIFIC GRAVITY : <b>2.65</b> IN ZERO AIR VOID CURVE CORRECTION OF MAXIMUM UNIT WEIGHT & OPTIMUM MOISTURE CONTENT FOR OVERSIZE PARTICLES : ASTM D4718 CORR. MAXIMUM DENSITY, LB/FT <sup>3</sup> <b>132.2</b> CORR. OPTIMUM MOISTURE, % <b>8.1</b>				
			DRY UNIT WEIGHT, LB/FT <sup>3</sup> 130.0 125.0 120.0 7.3 9.6 11.9 MOISTURE, % DRY WEIGHT				
TEST PROCEDURE			RESULT	SPECS	TEST PROCEDURE	RESULT	SPECS
<b>LIQUID &amp; PLASTIC PROPERTIES :</b> LIQUID LIMIT → ESTIMATED % RETAINED ON NO. 40 PLASTIC LIMIT → SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO PLASTICITY INDEX →					<b>RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :</b> GRADING 100 REV, % LOSS → GRADING 500 REV, % LOSS →		
<b>MOISTURE CONTENT :</b> PORTION TESTED % DRY WEIGHT →					<b>SPECIFIC GRAVITY :</b> MAX. PARTICLE SIZE, IN. SPECIFIC GRAVITY @ 20°C →		
<b>EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :</b> <input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % → MAXIMUM SWELL PRESSURE, KSF → SURCHARGE, KSF INITIAL WATER CONTENT, % DRY DENSITY, PCF					<b>pH DETERMINATION :</b> pH → <b>SOLUBLE SALTS :</b> PPM → <b>MINIMUM RESISTIVITY :</b> OHM-CM →		
<b>SOIL CLASSIFICATION :</b>			<b>GROUP SYMBOL:</b> <b>NAME:</b>				

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**

The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## LABORATORY REPORT

Client **ANDERSON ENGINEERING COMPANY, INC.**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Project **RICO INITIAL SOLIDS REMOVAL & DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **VARIOUS**  
Sample Source / Location **SSR-103**  
Reference: **ASTM**  
Special Instructions:

Date of Report **12-08-12**  
Job No. **3151JM098**  
Event / Invoice No. **31520185-15** Lab No.  
Authorized By **C. SANCHEZ** Date **10-22-12**  
Sampled By **CLIENT** Date **10-29-12**  
Submitted By **R. BORREGO** Date **11-07-12**  
Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT** Date **10-29-12**

### TEST RESULTS

<u>ELEVATION (FT)</u>	<u>MOISTURE CONTENT (%)</u>	<u>ATTERBERGS:</u>	<u>LL</u>	<u>PL</u>	<u>PI</u>	<u>ORGANIC CONTENT (%)</u>
0-5' BAGGIE	11.3					
10-13' BAGGIE	12.3					
25-30' BAGGIE	7.2					
5-35' BULK	2.4		28	20	8	
60-65' BAGGIE	10.8					
37-70' BULK	6.5					
80-86' BAGGIE	11.1					
70-87' BULK	8.8					

Comments: **SEE ADDITIONAL PHYSICAL PROPERTIES REPORTS FOR  
GRADATIONS**

Copies To: **CLIENT (2)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE  
WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE  
REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OF  
SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC.  
MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR  
IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE  
OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-10-12**

Job No. **3151JM098**

Event / Invoice No. **315200185-15**

Lab No. **0981109-**

Authorized By **C. SANCHEZ**

Date **10-22-12**

Sampled By **CLIENT**

Date **10-29-12**

Submitted By **R. BORREGO**

Date **11-07-12**

Project **RICO INITIAL SOLIDS**

Location **RICO, COLORADO**

Contractor **FLARE CONSTRUCTION**

Arch. / Engr. **ANDERSON ENGINEERING**

Type / Use of Aggregate **VARIABLE**

Supplier / Source **BORINGS**

Sample Source / Location **SSR-103 BULK 5-35'**

Source / Location Desig. By **CLIENT**

Date **10-29-12**

Special Instructions: **0981109-4**

### TEST RESULTS

SIEVE ANALYSIS			ASTM C136		AASHTO T27		PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION								
4 IN. - 100.0							UNIT WEIGHT & VOIDS			
3 - 75.0							FINE AGGREGATE		UNIT WEIGHT, PCF →	
2 - 50.0							VOIDS, % →			
1 1/2 - 37.5							COARSE AGGREGATE		UNIT WEIGHT, PCF →	
1 1/4 - 31.5							VOIDS, % →			
1 - 25.0	100						SPECIFIC GRAVITY & ABSORPTION			
3/4 - 19.0	84						FINE AGGREGATE		BULK SPECIFIC GRAVITY →	
1/2 - 12.5	71						ASTM C128 AASHTO T84		BULK SPECIFIC GRAVITY (SSD) →	
3/8 - 9.5	67						AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
1/4 - 6.3	61						YES NO		ABSORPTION, % →	
NO. 4 - 4.75	57						COARSE AGGREGATE		BULK SPECIFIC GRAVITY →	
8 - 2.36	50						ASTM C127 AASHTO T85		BULK SPECIFIC GRAVITY (SSD) →	
10 - 2.00	48						AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
16 - 1.18	44						YES NO		ABSORPTION, % →	
30 - .600	39						SAND EQUIVALENT VALUE		ASTM D2419 AASHTO T176 % →	
40 - .425	37						RESISTANCE TO DEGRADATION			
50 - .300	34						SMALL COARSE AGGREGATE		100 REV., % LOSS →	
100 - .150	26						ASTM C131 AASHTO T96 GRADING		500 REV., % LOSS →	
FINER THAN NO. 200							LARGE COARSE AGGREGATE		200 REV., % LOSS →	
ASTM C117							ASTM C535 GRADING		1000 REV., % LOSS →	
AASHTO T11							LIGHTWEIGHT PIECES			
FINENESS MODULUS, ASTM C125 →							FINE AGGREGATE, % →			
LIQUID & PLASTIC PROPERTIES							COARSE AGGREGATE, % →			
ASTM D4318 AASHTO T89 & T90							CLAY LUMPS & FRIABLE PARTICLES			
METHOD A B RESULT SPECIFICATION							FINE AGGREGATE, % →			
LIQUID LIMIT							COARSE AGGREGATE, % →			
PLASTIC LIMIT							FRACTURED FACES			
PLASTICITY INDEX							COARSE AGGREGATE BY WEIGHT		ONE OR MORE FACES, % →	
SAMPLE AIR DRIED YES NO							ASTM D5821 FLH T507 FAA		TWO OR MORE FACES, % →	
CLEANNESS VALUE CA227 →							DURABILITY INDEX			
ASTM D3744 AASHTO T210							PROCEDURE: A COARSE B FINE C COARSE & FINE		D <sub>c</sub> →	
ORGANIC IMPURITIES							UNCOMPACTED VOID CONTENT		ASTM C1252 % →	
ASTM C40 AASHTO T21							FLAT & ELONGATED PARTICLES		ASTM D4791 % →	
ORGANIC PLATE NO. →							DIMENSIONAL RATIO USED		1:2 1:3 1:5 % →	
CARBONATES IN AGGREGATE							BY WEIGHT, % →			
ARIZ 238 ASTM D3042 % →							BY NUMBER, % →			

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-10-12**  
Job No. **3151JM098**  
Event / Invoice No. **315200185-15**  
Authorized By **C. SANCHEZ**  
Sampled By **CLIENT**  
Submitted By **R. BORREGO**

Lab No. **0981109-**  
Date **10-22-12**  
Date **10-29-12**  
Date **11-07-12**

Project **RICO INITIAL SOLIDS**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Aggregate **VARIABLE**  
Sample Source / Location **SSR-103 BULK 37-70'**  
Special Instructions: **0981109-6**

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT**

Date **10-29-12**

### TEST RESULTS

SIEVE ANALYSIS			PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION				
4 IN. - 100.0			<b>UNIT WEIGHT &amp; VOIDS</b>			
3 - 75.0			FINE AGGREGATE		UNIT WEIGHT, PCF →	
2 - 50.0			<input type="checkbox"/> ASTM C29 <input type="checkbox"/> AASHTO T19		VOIDS, % →	
1 1/2 - 37.5			<input type="checkbox"/> RODDING <input type="checkbox"/> JIGGING <input type="checkbox"/> LOOSE		UNIT WEIGHT, PCF →	
1 1/4 - 31.5					VOIDS, % →	
1 - 25.0	<b>100</b>		<b>SPECIFIC GRAVITY &amp; ABSORPTION</b>			
3/4 - 19.0	<b>92</b>		FINE AGGREGATE		BULK SPECIFIC GRAVITY →	
1/2 - 12.5	<b>88</b>		<input type="checkbox"/> ASTM C128 <input type="checkbox"/> AASHTO T84		BULK SPECIFIC GRAVITY (SSD) →	
3/8 - 9.5	<b>83</b>		AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
1/4 - 6.3	<b>75</b>		<input type="checkbox"/> YES <input type="checkbox"/> NO		ABSORPTION, % →	
NO. 4 - 4.75	<b>71</b>		COARSE AGGREGATE		BULK SPECIFIC GRAVITY →	
8 - 2.36	<b>61</b>		<input type="checkbox"/> ASTM C127 <input type="checkbox"/> AASHTO T85		BULK SPECIFIC GRAVITY (SSD) →	
10 - 2.00	<b>60</b>		AGGREGATE DRIED		APPARENT SPECIFIC GRAVITY →	
16 - 1.18	<b>54</b>		<input type="checkbox"/> YES <input type="checkbox"/> NO		ABSORPTION, % →	
30 - .600	<b>49</b>		<b>SAND EQUIVALENT VALUE</b>			
40 - .425	<b>45</b>		<input type="checkbox"/> ASTM D2419 <input type="checkbox"/> AASHTO T176		% →	
50 - .300	<b>43</b>		<b>RESISTANCE TO DEGRADATION</b>			
100 - .150	<b>36</b>		SMALL COARSE AGGREGATE		100 REV., % LOSS →	
<b>FINER THAN NO. 200</b>	<b>29.0</b>		<input type="checkbox"/> ASTM C131 <input type="checkbox"/> AASHTO T96		500 REV., % LOSS →	
<input checked="" type="checkbox"/> ASTM C117			GRADING			
<input type="checkbox"/> AASHTO T11			LARGE COARSE AGGREGATE		200 REV., % LOSS →	
			<input type="checkbox"/> ASTM C535		1000 REV., % LOSS →	
<b>FINENESS MODULUS, ASTM C125 →</b>			<b>LIGHTWEIGHT PIECES</b>			
			<input type="checkbox"/> ASTM C123 <input type="checkbox"/> AASHTO T113		FINE AGGREGATE, % →	
					COARSE AGGREGATE, % →	
<b>LIQUID &amp; PLASTIC PROPERTIES</b>			<b>CLAY LUMPS &amp; FRIABLE PARTICLES</b>			
<input type="checkbox"/> ASTM D4318 <input type="checkbox"/> AASHTO T89 & T90			<input type="checkbox"/> ASTM C142 <input type="checkbox"/> AASHTO T112		FINE AGGREGATE, % →	
METHOD <input type="checkbox"/> A <input type="checkbox"/> B RESULT SPECIFICATION					COARSE AGGREGATE, % →	
LIQUID LIMIT						
PLASTIC LIMIT						
PLASTICITY INDEX						
SAMPLE AIR DRIED <input type="checkbox"/> YES <input type="checkbox"/> NO						
<b>CLEANNES VALUE</b> CA227 →			<b>FRACTURED FACES</b>			
			COARSE AGGREGATE BY WEIGHT		ONE OR MORE FACES, % →	
			<input type="checkbox"/> ASTM D5821 <input type="checkbox"/> FLH T507 <input type="checkbox"/> FAA <input type="checkbox"/>		TWO OR MORE FACES, % →	
<b>ORGANIC IMPURITIES</b> <input type="checkbox"/> ASTM C40 <input type="checkbox"/> AASHTO T21			<b>DURABILITY INDEX</b> <input type="checkbox"/> ASTM D3744 <input type="checkbox"/> AASHTO T210		D <sub>c</sub> →	
ORGANIC PLATE NO. →			PROCEDURE: A <input type="checkbox"/> COARSE B <input type="checkbox"/> FINE C <input type="checkbox"/> COARSE & FINE		D <sub>f</sub> →	
			<b>UNCOMPACTED VOID CONTENT</b> <input type="checkbox"/> ASTM C1252 <input type="checkbox"/>		% →	
<b>CARBONATES IN AGGREGATE</b>			<b>FLAT &amp; ELONGATED PARTICLES</b> <input type="checkbox"/> ASTM D4791 <input type="checkbox"/>		BY WEIGHT, % →	
<input type="checkbox"/> ARIZ 238 <input type="checkbox"/> ASTM D3042 % →			DIMENSIONAL RATIO USED <input type="checkbox"/> 1:2 <input type="checkbox"/> 1:3 <input type="checkbox"/> 1:5 <input type="checkbox"/>		BY NUMBER, % →	

Comments:

Copies To: **CLIENT (2) - ELECTRONIC**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Project **RICO INITIAL SOLIDS**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Aggregate **VARIABLE**  
Sample Source / Location **SSR-103 BULK 70-87'**  
Special Instructions: **0981109-8**

Date of Report **12-10-12**  
Job No. **3151JM098**  
Event / Invoice No. **315200185-15**  
Authorized By **C. SANCHEZ**  
Sampled By **CLIENT**  
Submitted By **R. BORREGO**  
Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **BORINGS**  
Source / Location Desig. By **CLIENT**  
Lab No. **0981109-**  
Date **10-22-12**  
Date **10-29-12**  
Date **11-07-12**  
Date **10-29-12**

### TEST RESULTS

SIEVE ANALYSIS			PHYSICAL PROPERTIES		TEST RESULTS	SPECIFICATION
SIEVE SIZE U.S. - MM	ACCUMULATIVE % PASSING	SPECIFICATION				
4 IN. - 100.0			UNIT WEIGHT & VOIDS			
3 - 75.0			FINE AGGREGATE		UNIT WEIGHT, PCF →	
2 - 50.0			COARSE AGGREGATE		VOIDS, % →	
1 1/2 - 37.5					UNIT WEIGHT, PCF →	
1 1/4 - 31.5					VOIDS, % →	
1 - 25.0			SPECIFIC GRAVITY & ABSORPTION			
3/4 - 19.0	100		FINE AGGREGATE		BULK SPECIFIC GRAVITY →	
1/2 - 12.5	97		BULK SPECIFIC GRAVITY (SSD) →			
3/8 - 9.5	94		APPARENT SPECIFIC GRAVITY →			
1/4 - 6.3	88		ABSORPTION, % →			
NO. 4 - 4.75	83		COARSE AGGREGATE		BULK SPECIFIC GRAVITY →	
8 - 2.36	73		BULK SPECIFIC GRAVITY (SSD) →			
10 - 2.00	71		APPARENT SPECIFIC GRAVITY →			
16 - 1.18	64		ABSORPTION, % →			
30 - .600	57		SAND EQUIVALENT VALUE			
40 - .425	54		ASTM D2419 AASHTO T176		% →	
50 - .300	50		RESISTANCE TO DEGRADATION			
100 - .150	42		SMALL COARSE AGGREGATE		100 REV., % LOSS →	
			ASTM C131 AASHTO T96 GRADING		500 REV., % LOSS →	
			LARGE COARSE AGGREGATE		200 REV., % LOSS →	
			ASTM C535 GRADING		1000 REV., % LOSS →	
			LIGHTWEIGHT PIECES			
			ASTM C123 AASHTO T113		FINE AGGREGATE, % →	
					COARSE AGGREGATE, % →	
			CLAY LUMPS & FRIABLE PARTICLES			
			ASTM C142 AASHTO T112		FINE AGGREGATE, % →	
					COARSE AGGREGATE, % →	
			FRACTURED FACES			
			ASTM D5821 FLH T507 FAA		ONE OR MORE FACES, % →	
					TWO OR MORE FACES, % →	
			CLEANNESS VALUE			
			CA227 →			
			DURABILITY INDEX			
			ASTM D3744 AASHTO T210		D <sub>c</sub> →	
			PROCEDURE: A COARSE B FINE C COARSE & FINE		D <sub>f</sub> →	
			ORGANIC IMPURITIES			
			ASTM C40 AASHTO T21			
			UNCOMPACTED VOID CONTENT			
			ASTM C1252		% →	
			CARBONATES IN AGGREGATE			
			ASTM D3042		BY WEIGHT, % →	
			FLAT & ELONGATED PARTICLES		BY NUMBER, % →	
			ASTM D4791			
			DIMENSIONAL RATIO USED			
			1:2 1:3 1:5			

Comments:

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY



## **Soils Testing**

### *2. Samples from Test Pits*

TP-2004A

TP-2004B

TP2011-AT1

TP2011-AT2

TP2011-AT3

TP2011-AT4

TP2011-AT5

TP2011-AT6

TP2011-17

TP-17

TP-18

TP-22

TP-2013XX

TP-2013YY

TP-2013Z





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-09-11**  
Job No. **3151JM098**  
Event / Invoice No. **31510186-106**  
Authorized by **CHRIS SANCHEZ**  
Sampled by **CLIENT**  
Submitted by **D. SENJEM**

Lab No. **0981104-1**  
Date **10-21-11**  
Date **10-21-11**  
Date **10-31-11**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **4" MINUS SILTY CLAYEY SAND W/GRAV.**  
Sample Source / Location **TP-1 (TP2011-AT1)**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **EXISTING SUBGRADE**  
Source / Location Desig. By **CLIENT**

Date **10-21-11**

### TEST RESULTS

SIEVE ANALYSIS : ASTM C136 FINER THAN NO. 200 : ASTM C117			LABORATORY COMPACTION CHARACTERISTICS : ASTM D698 METHOD C								
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION				SAMPLE PREPARATION: <input checked="" type="checkbox"/> WET <input type="checkbox"/> DRY					
						RAMMER USED: <input checked="" type="checkbox"/> 2 IN. CIRCULAR FACE <input type="checkbox"/> OTHER <input type="checkbox"/> MECHANICAL <input checked="" type="checkbox"/> MANUAL					
6			<p>PROJECT PROCTOR ID: <b>42</b>            MAXIMUM DENSITY, LBF/FT<sup>3</sup> → <b>122.6</b>            OPTIMUM MOISTURE CONTENT, % → <b>10.5</b></p> <p>OVERSIZE AGGREGATE :            ASSUMED BULK SPECIFIC GRAVITY : <b>2.65</b>            ASSUMED ABSORPTION, % : <b>1.0</b>            % OVERSIZE IN LAB SAMPLE : <b>14</b></p> <p>ASSUMED SPECIFIC GRAVITY            IN ZERO AIR VOID CURVE : <b>2.65</b></p> <p>CORRECTION OF MAXIMUM UNIT WEIGHT &amp;            OPTIMUM MOISTURE CONTENT FOR OVERSIZE            PARTICLES : ASTM D4718</p> <p>CORR. MAXIMUM DENSITY, LBF/FT<sup>3</sup> <b>127.2</b>            CORR. OPTIMUM MOISTURE, % <b>9.2</b></p>			SAMPLE PREPARATION: <input checked="" type="checkbox"/> WET <input type="checkbox"/> DRY RAMMER USED: <input checked="" type="checkbox"/> 2 IN. CIRCULAR FACE <input type="checkbox"/> OTHER <input type="checkbox"/> MECHANICAL <input checked="" type="checkbox"/> MANUAL					
5											
4	100										
3	96										
2	96										
1 1/2	94										
1	89										
3/4	86										
1/2	81										
3/8	77										
1/4	70										
No.4	68										
8	55										
10	55										
16	48										
30	41										
40	38										
50	35										
100	28										
200	23										
TEST PROCEDURE			RESULT	SPECS	TEST PROCEDURE			RESULT	SPECS		
LIQUID & PLASTIC PROPERTIES : AASHTO T89, 90						RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :					
METHOD B						GRADING 100 REV, % LOSS →					
ESTIMATED % RETAINED ON NO. 40 62						GRADING 500 REV, % LOSS →					
SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO											
PLASTIC LIMIT → 18											
PLASTICITY INDEX → 6											
MOISTURE CONTENT :						SPECIFIC GRAVITY :					
PORTION TESTED						MAX. PARTICLE SIZE, IN.			SPECIFIC GRAVITY @ 20 °C →		
% DRY WEIGHT →						pH DETERMINATION :			pH →		
EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :						SOLUBLE SALTS :			PPM →		
<input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % →						MINIMUM RESISTIVITY :			OHM-CM →		
MAXIMUM SWELL PRESSURE, KSF →											
SURCHARGE, KSF											
INITIAL WATER CONTENT, %											
DRY DENSITY, PCF											
SOIL CLASSIFICATION : ASTM D2487			GROUP SYMBOL: <b>SC-SM</b>								
			NAME: <b>SILTY, CLAYEY SAND WITH GRAVEL</b>								

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-07-11**  
Job No. **3151JM098**  
Event / Invoice No. **31510186-95** Lab No. **0981129-2**  
Authorized by **CHRIS SANCHEZ** Date **10-21-11**  
Sampled by **CLIENT** Date **10-21-11**  
Submitted by **D. SENJEM** Date **10-31-11**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **3" MINUS SILTY GRAVEL WITH SAND**  
Sample Source / Location **TP-2 (TP2011-AT2)**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **EXISTING SUBGRADE**  
Source / Location Desig. By **CLIENT** Date **10-21-11**

### TEST RESULTS

SIEVE ANALYSIS : CP-31 FINER THAN NO. 200 : ASTM C117			LABORATORY COMPACTION CHARACTERISTICS : ASTM D698 METHOD C		
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION			
6					
5					
4					
3	100				
2	90				
1 1/2	84				
1	77				
3/4	72				
1/2	66				
3/8	64				
1/4	58				
No. 4	54				
8	45				
10	42				
16	37				
30	31				
40	28				
50	25				
100	21				
200	17				

SAMPLE PREPARATION: <input checked="" type="checkbox"/> WET <input type="checkbox"/> DRY RAMMER USED: <input checked="" type="checkbox"/> 2 IN. CIRCULAR FACE <input type="checkbox"/> OTHER <input type="checkbox"/> MECHANICAL <input checked="" type="checkbox"/> MANUAL		PROJECT PROCTOR ID: <b>38</b> MAXIMUM DENSITY, LBF/FT <sup>3</sup> → <b>129.7</b> OPTIMUM MOISTURE CONTENT, % → <b>10.2</b>
OVERSIZE AGGREGATE : ASSUMED BULK SPECIFIC GRAVITY : <b>2.65</b> ASSUMED ABSORPTION, % : <b>1.0</b> % OVERSIZE IN LAB SAMPLE : <b>28</b>		ASSUMED SPECIFIC GRAVITY IN ZERO AIR VOID CURVE : <b>2.71</b>
CORRECTION OF MAXIMUM UNIT WEIGHT & OPTIMUM MOISTURE CONTENT FOR OVERSIZE PARTICLES : ASTM D4718		
CORR. MAXIMUM DENSITY, LBF/FT <sup>3</sup> : <b>138.0</b> CORR. OPTIMUM MOISTURE, % : <b>7.6</b>		

TEST PROCEDURE	RESULT	SPECS	TEST PROCEDURE	RESULT	SPECS
<b>LIQUID &amp; PLASTIC PROPERTIES : ASTM D4318</b> METHOD B LIQUID LIMIT → <b>21</b> ESTIMATED % RETAINED ON NO. 40 <b>72</b> PLASTIC LIMIT → <b>0</b> SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO PLASTICITY INDEX → <b>NP</b>			<b>RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :</b> GRADING 100 REV, % LOSS → GRADING 500 REV, % LOSS →		
<b>MOISTURE CONTENT :</b> PORTION TESTED % DRY WEIGHT →			<b>SPECIFIC GRAVITY :</b> MAX. PARTICLE SIZE, IN. SPECIFIC GRAVITY @ 20°C →		
<b>EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :</b> <input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % → MAXIMUM SWELL PRESSURE, KSF →			<b>pH DETERMINATION :</b> pH →		
SURCHARGE, KSF INITIAL WATER CONTENT, % DRY DENSITY, PCF			<b>SOLUBLE SALTS :</b> PPM →		
			<b>MINIMUM RESISTIVITY :</b> OHM-CM →		

<b>SOIL CLASSIFICATION : ASTM D2487</b> <b>GROUP SYMBOL: GM</b> <b>NAME: SILTY GRAVEL WITH SAND</b>
---

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-07-11**

Job No. **3151JM098**

Event / Invoice No. **31510186-96**

Lab No. **0981104-3**

Authorized by **CHRIS SANCHEZ**

Date **10-21-11**

Sampled by **CLIENT**

Date **10-21-11**

Submitted by **D. SENJEM**

Date **10-31-11**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **3' MINUS SILTY GRAVEL WITH SAND**  
Sample Source / Location **TP-3 (TP2011-AT3)**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **EXISTING SUBGRADE**  
Source / Location Desig. By **CLIENT**

Date **10-21-11**

### TEST RESULTS

SIEVE ANALYSIS : ASTM C136 FINER THAN NO. 200 : ASTM C117			LABORATORY COMPACTION CHARACTERISTICS : ASTM D698 METHOD C		
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION			
6					
5					
4					
3	100				
2	98				
1 1/2	95				
1	88				
3/4	82				
1/2	81				
3/8	65				
1/4	56				
No.4	51				
8	39				
10	38				
16	31				
30	26				
40	24				
50	21				
100	17				
200	13				

SAMPLE PREPARATION: <input checked="" type="checkbox"/> WET <input type="checkbox"/> DRY RAMMER USED: <input checked="" type="checkbox"/> 2 IN. CIRCULAR FACE <input type="checkbox"/> OTHER <input type="checkbox"/> MECHANICAL <input checked="" type="checkbox"/> MANUAL		PROJECT PROCTOR ID: <b>12</b> MAXIMUM DENSITY, LBF/FT <sup>3</sup> → <b>130.5</b> OPTIMUM MOISTURE CONTENT, % → <b>9.8</b>	
OVERSIZE AGGREGATE : ASSUMED BULK SPECIFIC GRAVITY : <b>2.65</b> ASSUMED ABSORPTION, % : <b>1.0</b> % OVERSIZE IN LAB SAMPLE : <b>18</b>		ASSUMED SPECIFIC GRAVITY IN ZERO AIR VOID CURVE : <b>2.72</b>	
CORRECTION OF MAXIMUM UNIT WEIGHT & OPTIMUM MOISTURE CONTENT FOR OVERSIZE PARTICLES : ASTM D4718			
CORR. MAXIMUM DENSITY, LBF/FT <sup>3</sup> : <b>135.6</b> CORR. OPTIMUM MOISTURE, % : <b>8.2</b>			

TEST PROCEDURE	RESULT	SPECS	TEST PROCEDURE	RESULT	SPECS
<b>LIQUID &amp; PLASTIC PROPERTIES : AASHTO T89, 90</b> METHOD B LIQUID LIMIT → ESTIMATED % RETAINED ON NO. 40 77 PLASTIC LIMIT → SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO PLASTICITY INDEX →			<b>RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :</b> GRADING 100 REV, % LOSS → GRADING 500 REV, % LOSS →		
<b>MOISTURE CONTENT :</b> PORTION TESTED % DRY WEIGHT →			<b>SPECIFIC GRAVITY :</b> MAX. PARTICLE SIZE, IN. SPECIFIC GRAVITY @ 20°C →		
<b>EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :</b> <input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % MAXIMUM SWELL PRESSURE, KSF → SURCHARGE, KSF INITIAL WATER CONTENT, % DRY DENSITY, PCF			<b>pH DETERMINATION :</b> pH → <b>SOLUBLE SALTS :</b> PPM → <b>MINIMUM RESISTIVITY :</b> OHM-CM →		
<b>SOIL CLASSIFICATION : ASTM D2487</b>			<b>GROUP SYMBOL: GM</b> <b>NAME: SILTY GRAVEL WITH SAND</b>		

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-07-11**  
Job No. **3151JM098**  
Event / Invoice No. **31510186-97** Lab No. **0981104-4**  
Authorized by **CHRIS SANCHEZ** Date **10-21-11**  
Sampled by **CLIENT** Date **10-21-11**  
Submitted by **D. SENJEM** Date **10-31-11**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **4' MINUS SILTY GRAVEL WITH SAND**  
Sample Source / Location **TP-5 (TP2011-AT5)**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **EXISTING GROUND**  
Source / Location Desig. By **CLIENT** Date **10-21-11**

### TEST RESULTS

SIEVE ANALYSIS : ASTM C136 FINER THAN NO. 200 : ASTM C117			LABORATORY COMPACTION CHARACTERISTICS : ASTM D698 METHOD C		
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION			
6					
5					
4	100				
3	89				
2	86				
1 1/2	81				
1	72				
3/4	67				
1/2	62				
3/8	58				
1/4	53				
No.4	50				
8	44				
10	43				
16	39				
30	35				
40	32				
50	30				
100	25				
200	19				

SAMPLE PREPARATION: <input checked="" type="checkbox"/> WET <input type="checkbox"/> DRY RAMMER USED: <input checked="" type="checkbox"/> 2 IN. CIRCULAR FACE <input type="checkbox"/> OTHER <input type="checkbox"/> MECHANICAL <input checked="" type="checkbox"/> MANUAL		PROJECT PROCTOR ID: <b>16</b> MAXIMUM DENSITY, LBF/FT <sup>3</sup> → <b>121.8</b> OPTIMUM MOISTURE CONTENT, % → <b>12.1</b>
OVERSIZE AGGREGATE : ASSUMED BULK SPECIFIC GRAVITY : <b>2.65</b> ASSUMED ABSORPTION, % : <b>1.0</b> % OVERSIZE IN LAB SAMPLE : <b>33</b>		ASSUMED SPECIFIC GRAVITY IN ZERO AIR VOID CURVE : <b>2.67</b>
CORRECTION OF MAXIMUM UNIT WEIGHT & OPTIMUM MOISTURE CONTENT FOR OVERSIZE PARTICLES : ASTM D4718		
CORR. MAXIMUM DENSITY, LBF/FT <sup>3</sup> : <b>133.4</b> CORR. OPTIMUM MOISTURE, % : <b>8.4</b>		

TEST PROCEDURE	RESULT	SPECS	TEST PROCEDURE	RESULT	SPECS
<b>LIQUID &amp; PLASTIC PROPERTIES : AASHTO T89, 90</b> METHOD B LIQUID LIMIT → <b>35</b> ESTIMATED % RETAINED ON NO. 40 <b>68</b> PLASTIC LIMIT → <b>27</b> SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO PLASTICITY INDEX → <b>8</b>			<b>RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :</b> GRADING 100 REV, % LOSS → GRADING 500 REV, % LOSS →		
<b>MOISTURE CONTENT :</b> PORTION TESTED % DRY WEIGHT →			<b>SPECIFIC GRAVITY :</b> MAX. PARTICLE SIZE, IN. SPECIFIC GRAVITY @ 20°C →		
<b>EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :</b> <input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % → MAXIMUM SWELL PRESSURE, KSF →			<b>pH DETERMINATION :</b> pH →		
SURCHARGE, KSF INITIAL WATER CONTENT, % DRY DENSITY, PCF			<b>SOLUBLE SALTS :</b> PPM →		
			<b>MINIMUM RESISTIVITY :</b> OHM-CM →		
<b>SOIL CLASSIFICATION : ASTM D2487</b>			<b>GROUP SYMBOL: GM</b> <b>NAME: SILTY GRAVEL WITH SAND</b>		

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY





**Western  
Technologies  
Inc.**  
The Quality People  
Since 1955

278 Sawyer Drive, No. 2  
Durango, Colorado 81302  
(970) 375-9033 • fax: 375-9034

## PHYSICAL PROPERTIES OF SOILS & AGGREGATES

Client **ANDERSON ENGINEERING**  
**977 WEST 2100 SOUTH**  
**SALT LAKE CITY, UT 84119**

Date of Report **12-09-11**

Job No. **3151JM098**

Event / Invoice No. **31510186-107**

Lab No. **0981104-5**

Authorized by **CHRIS SANCHEZ**

Date **10-21-11**

Sampled by **CLIENT**

Date **10-21-11**

Submitted by **D. SENJEM**

Date **10-31-11**

Project **RICO INITIAL SOLIDS REMOVAL AND DRYING**  
Contractor **FLARE CONSTRUCTION**  
Type / Use of Material **3" MINUS CLAYEY GRAVEL WITH SAND**  
Sample Source / Location **TP-6 (TP2011-AT6)**  
Testing Authorized :  
Special Instructions :

Location **RICO, COLORADO**  
Arch. / Engr. **ANDERSON ENGINEERING**  
Supplier / Source **EXISTING SUBGRADE**  
Source / Location Desig. By **CLIENT**

Date **10-21-11**

### TEST RESULTS

SIEVE ANALYSIS : CP-31 FINER THAN NO. 200 : ASTM C117			LABORATORY COMPACTION CHARACTERISTICS : ASTM D698 METHOD C					
SIEVE	ACCUMULATIVE % PASSING	SPECIFICATION			SAMPLE PREPARATION: <input checked="" type="checkbox"/> WET <input type="checkbox"/> DRY			
					RAMMER USED: <input checked="" type="checkbox"/> 2 IN. CIRCULAR FACE <input type="checkbox"/> OTHER <input type="checkbox"/> MECHANICAL <input checked="" type="checkbox"/> MANUAL			
6			<p>PROJECT PROCTOR ID: <b>41</b> MAXIMUM DENSITY, LBF/FT<sup>3</sup> → <b>123.9</b> OPTIMUM MOISTURE CONTENT, % → <b>11.3</b></p> <p>OVERSIZE AGGREGATE : ASSUMED BULK SPECIFIC GRAVITY : <b>2.65</b> ASSUMED ABSORPTION, % : <b>1.0</b> % OVERSIZE IN LAB SAMPLE : <b>19</b></p> <p>ASSUMED SPECIFIC GRAVITY IN ZERO AIR VOID CURVE : <b>2.65</b></p> <p><b>CORRECTION OF MAXIMUM UNIT WEIGHT &amp; OPTIMUM MOISTURE CONTENT FOR OVERSIZE PARTICLES : ASTM D4718</b></p> <p>CORR. MAXIMUM DENSITY, LBF/FT<sup>3</sup> <b>130.1</b> CORR. OPTIMUM MOISTURE, % <b>9.3</b></p>					
5								
4	100							
3	98							
2	94							
1 1/2	91							
1	85							
3/4	81							
1/2	74							
3/8	71							
1/4	64							
No.4	60							
8	50							
10	49							
16	42							
30	37							
40	34							
50	32							
100	27							
200	22							
TEST PROCEDURE			RESULT	SPECS	TEST PROCEDURE	RESULT	SPECS	
LIQUID & PLASTIC PROPERTIES : AASHTO T89, 90					RESISTANCE TO DEGRADATION OF SMALL-SIZE COARSE AGGREGATES BY ABRASION :			
METHOD B LIQUID LIMIT →			32		GRADING 100 REV, % LOSS →			
ESTIMATED % RETAINED ON NO. 40 66 PLASTIC LIMIT →			21		GRADING 500 REV, % LOSS →			
SAMPLE AIR DRIED <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO PLASTICITY INDEX →			11					
MOISTURE CONTENT :					SPECIFIC GRAVITY :			
PORTION TESTED % DRY WEIGHT →					MAX. PARTICLE SIZE, IN. SPECIFIC GRAVITY @ 20°C →			
EXPANSION / COMPRESSION PROPERTIES OF COHESIVE SOIL :					pH DETERMINATION :			
<input type="checkbox"/> EXPANSION <input type="checkbox"/> COMPRESSION, % →					pH →			
MAXIMUM SWELL PRESSURE, KSF →					SOLUBLE SALTS :			
SURCHARGE, KSF					PPM →			
INITIAL WATER CONTENT, % DRY DENSITY, PCF					MINIMUM RESISTIVITY :			
					OHM-CM →			
SOIL CLASSIFICATION : ASTM D2487			GROUP SYMBOL: GC					
			NAME: CLAYEY GRAVEL WITH SAND					

Comments :

Copies to : **CLIENT (1)**

THE SERVICES REFERRED TO HEREIN WERE PERFORMED IN ACCORDANCE WITH THE STANDARD OF CARE PRACTICED LOCALLY FOR THE REFERENCED METHOD(S) AND RELATE ONLY TO THE CONDITION(S) OR SAMPLE(S) TESTED AS STATED HEREIN. WESTERN TECHNOLOGIES INC. MAKES NO OTHER WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, AND HAS NOT CONFIRMED INFORMATION INCLUDING SOURCE OF MATERIALS SUBMITTED BY OTHERS.

REVIEWED BY